

TECHNICAL DRAINAGE STUDY

for

Area 1, Phases A & B

Golden Valley Ranch

Mohave County, AZ

Prepared for:

Rhodes Homes Arizona, LLC.

2215 Hualapai Mountain Rd., Suite H

Kingman, Arizona 86401



Stanley Consultants INC.

A Stanley Group Company
Engineering, Environmental and Construction Services - Worldwide

Technical Drainage Study

For

**Area 1, Phases A & B
Golden Valley Ranch
Mohave County, AZ**

**March 2006
SCI Project # 18449.00.00**

Prepared for:

**Rhodes Homes Arizona, LLC.
2215 Hualapai Mountain Road, Suite H
Kingman, Arizona 86401**

Prepared By:

**STANLEY CONSULTANTS, INC.
5820 South Eastern Avenue, Suite 200
Las Vegas, Nevada 89119
(702)369-9396
Fax (702)369-9793**



GOLDEN VALLEY RANCH

TABLE OF CONTENTS

1.	GENERAL LOCATION AND DEVELOPMENT DESCRIPTION	1
1.1.	Introduction	1
1.2.	Location.....	1
1.3.	FEMA Flood Hazard Zone.....	1
2.	SITE DESCRIPTION.....	1
2.1.	Description of Property	1
2.2.	Drainage Descriptions	4
3.	METHODS AND CRITERIA	4
3.1.	Methodology	4
3.2.	Drainage Shed and Modeling Convention	6
3.3.	Design Storm and Precipitation.....	6
3.4.	Soils.....	7
3.5.	Model Data and Results	7
4.	Drainage Improvements within the Public Right-of-Way	9
5.	Comparison of Flows	9
6.	FEMA Base Flood Elevations	12
7.	SUMMARY	12
8.	REFERENCES.....	12

GOLDEN VALLEY RANCH

LIST OF TABLES

Table 1 - Precipitation	7
Table 2 –Flow Summary	8
Table 3 – Flow Comparison	9

LIST OF FIGURES

Figure 1 – Vicinity Map and Regional Drainage Scheme	2
Figure 2 - Flood Insurance Rate Map, Mohave County, Arizona	3
Figure 3 – Area 1 Drainage Shed Map.....	5
Figure 4 – Drainage Improvements within Public Right-of-Way	10
Figure 5 – Existing Runoff - Flow Comparison	11
Figure 6 – Base Flood Elevation (BFE).....	13

GOLDEN VALLEY RANCH

APPENDICES

Appendix A Area 1 – Results and Data

- HEC-HMS 100-yr, 6-hr Simulation
- HEC-HMS 10-yr, 6-hr Simulation
- NOAA Atlas 14 – Precipitation
- STANDARD FORM 4 – Time of Concentration

Appendix B Drainage Infrastructure Calculations

- COMMON LOT O (P1-83)
- COMMON LOT F (J-C14)
- COMMON LOT E (J-C17)
- H STREET (J-C21)
- COMMON LOT D (J-C25)

Appendix C Street Capacity (Local Streets)

Appendix D Public Right-of-Way Drainage Improvements

- INLET CALCULATIONS
- HYDRAULIC CALCULATIONS – WEST LOOP ROAD
- CULVERT CAPACITY (J-C26, J-N5, J-N25, J-H, & J-N2)

Appendix E Base Flood Elevations (BFE) – HecRAS output

**Appendix F Plans - Not Included with this Study
(See Grading Plans this Project)**

GOLDEN VALLEY RANCH**1. GENERAL LOCATION AND DEVELOPMENT DESCRIPTION****1.1. Introduction**

This study is submitted as the technical drainage study for the proposed improvement plans of Area 1, Phases A & B of the Golden Valley Ranch residential development located in the Sacramento Valley of Mohave County, Arizona, more specifically on the south side of the Golden Valley Community, near Kingman. Area 1 comprises of approximately 187 acres of the total 5,800 acres of land located in the Golden Valley Ranch.

The purpose of this study is to evaluate the storm drainage infrastructure of the proposed development for Area 1, Phase A only. Phase B improvements will be submitted at a later date. Documentation for Phase B is included to provide continuity in the infrastructure improvements.

This study is divided into four separate areas of consideration. They are as follows:

- A general overview of site drainage
- A detailed analysis of the proposed storm drainage infrastructure.
- An analysis of the drainage improvements in the Public Right-of-Way.
- An evaluation of interim facilities serving the site

1.2. Location

The Golden Valley Ranch project site consists of Taxpin Numbers 215-01-048, 215-01-075, 215-01-078, 215-01-079, 215-01-080, 215-01-084, 215-01-085, 215-01-092, & 215-15-005 within Township 20 North, Range 18 West and Township 21 North, and Range 18 West, G&SRM, Mohave County, Arizona (Figure 1 - Vicinity Map and Regional Drainage Scheme).


1.3. FEMA Flood Hazard Zone

Figure 2 is a representation of the Federal Emergency Management Agency (FEMA) Flood Insurance Rate Map (FIRM) for Mohave County, AZ, map number 040058 2325C, dated October 20, 2000. Of the 187 acres of Area 1, 25 acres lies in Special Flood Hazard Zone A.

Zone A is the flood insurance rate zone that corresponds to the 100-year floodplains that are determined in the Flood Insurance Study (FIS) by approximate methods. Because detailed hydraulic analyses are not performed for such areas, no Base Flood Elevations (BFE's) or depths are shown within this zone. Mandatory flood insurance purchase requirements apply.


2. SITE DESCRIPTION**2.1. Description of Property**







The property is semiarid rangeland with a covering of desert shrub in poor condition. Area 1, Phases A & B is located generally in the southwest quadrant of Section 4, Township 20 North, Range 18 West, G&SRM, with minor portions in Sections 3 and 9. The project will be



GOLDEN VALLEY RANCH — WASH FLOW SUMMARY				
(100%, 24 hr PRECIPITATION)				
BASIN/NODE	UPSTREAM SITED AREA (Sq. Mi.)	FLOW (CFS)	BASIN/NODE	UPSTREAM SITED AREA (Sq. Mi.)
HM-A	36.68	12,987	J-A	289.99
HM-B	11.68	7,668	J-B	136.79
HM-C	4.53	3,154	J-C	9,862
HM-D	4.44	2,042	J-D	8,261
HM-E	3.40	1,197	J-E	51.13
HM-F	0.25	242	J-F	38.04
HM-G	12.08	5,177	J-G	60.72
HM-H	4.33	3,862	J-H	57.32
HM-I	2.41	1,304	J-I	52.88
HM-J	3.05	1,540	J-K	48.36
HM-K	3.87	1,255	J-L	5,177
HM-L	3.56	2,519	J-M	12.08
HM-M	2.55	1,255	J-N	15.78
HM-N	2.50	660	J-P	9.76
HM-O	3.31	2,184	J-Q	7.33
HM-P	6.00	1,887	J-R	7.43
HM-Q	3.78	364	J-S	13.09
HM-R	7.12	3,913	J-T	9.31
HM-S	4.18	1,048	J-U	16.24
HM-T	4.94	1,035	J-V	11.29
HM-U	1.05	655	J-W	153.19
HM-V			J-X	146.13
HM-W			J-Y	14.70







 **Stanley Consultants** INC.
5820 S. EASTERN AVENUE, SUITE 200
LAS VEGAS, NEVADA 89119 (702) 369-9396

**GOLDEN VALLEY RANCH
AREA 1 DRAINAGE SUB-SHEDS
TECHNICAL DRAINAGE STUDY EXHIBIT**

MOHAVE COUNTY

ARIZONA

FIGURE 3

ST-RH036312

GOLDEN VALLEY RANCH

components. Each component models an aspect of the rainfall-runoff process within a portion of the whole basin. This basin portion is referred to as a sub-basin. The runoff hydrographs of each sub-basin are then combined and a final discharge hydrograph is obtained. It was chosen as the hydrology model since it is the model used in a Preliminary Federal Insurance Study prepared for Mohave County Flood Control District, October 2005 for various watersheds in the Golden Valley and Kingman, AZ area. This adds consistency and reliability in the methodology. Modified-Puls routing in the HEC-HMS model allows for retardation of peak flows within the broad flood way of the golf course.

HEC-RAS, another program from the COE, provides a steady state flow analysis to determine water surface elevations within a defined channel or flood plain. Volume computations within the HEC-RAS program were utilized in developing flow routing by Modified-Puls methods.

Water Surface Pressure Gradient (WSPG) program developed by the Los Angeles County Flood Control District. WSPG is a similar program to HEC-RAS in that it develops the water surface elevations and other channel parameters, but is better adapted to closed (pressure) conduit flow and is therefore used in the evaluation of the stormwater infrastructure system.

Calculations for street capacity are produced using the FlowMaster by Haestad Methods, Inc. Inlet calculations are performed using Federal Highway Administration's Visual Urban program for pavement drainage.

3.2. Drainage Shed and Modeling Convention

The basic naming convention of the basins for the exhibits and model are based around the individual drainage shed of the development. Sheds are labeled as P1-34, identifying Area 1, Shed 34. Junction points or points of runoff confluence are identified as J-C12, identifying that it is a junction point and a label. An R designates a routing of a shed or junction, therefore R-JN15 represents routing of junction JN15 to another point.

3.3. Design Storm and Precipitation

Local jurisdiction requires that water sheds less than 20 square miles be evaluated for the 6-hour local storm. Drainage sheds of 20 to 100 square miles are to be evaluated for both the 6-hour and 24-hour rainfall events. Areas from 20 square miles to 500 square miles are considered general storms and are evaluated for the 24-hour precipitation.

Maricopa County Flood Control District has developed storm distribution curves associated with drainage shed size. Since the total area of Area 1, Phases A & B is less than 1 square mile, Pattern 1 of the Maricopa County 6-Hour Mass Curve was utilized for the storm distribution. Precipitation values of 3.00-inches and 1.76-inches were taken from the National Oceanographic and Atmospheric Administration National Weather Service's Atlas 14. Table 4 provides the precipitation values from NOAA Atlas 14. Since the total area of Area 1 is 0.29 square miles (187 acres) the depth-area reduction factor was not applied.

GOLDEN VALLEY RANCH**Table 1 - Precipitation**

Recurrence Interval (yrs)	5 min	10-min	15-min	30-min	1-hr	2-hr	3-hr	6-hr
10-yr	0.40	0.61	0.75	1.01	1.25	1.44	1.53	1.76
100-yr	0.65	0.98	1.22	1.64	2.03	2.44	2.67	3.00

3.4. Soils

Soils information is taken from the statewide coverage for Arizona, 2005, Natural Resources Conservation Service, Soil Data Mart. Soils within Area 1, Phases A & B consist of CACIQUE-BUCKLEBAR-ALKO (AZ039) type. These soils have a hydrologic soil type designation of "C".

3.5. Model Data and Results

Table 2 summarizes runoff at junction points and drainage sheds within Area 1, Phases A & B. Runoff values are rounded to the nearest 1 cfs.

GOLDEN VALLEY RANCH**Table 2 –Flow Summary**

Element	Area (sq mi)	Peak Discharge 100-yr (cfs)	Peak Discharge 10-yr (cfs)	Element	Area (sq mi)	Peak Discharge 100-yr (cfs)	Peak Discharge 10-yr (cfs)
J-C01	0.0268	57	21	P1-67	0.0107	24	9
J-C02	0.0341	71	25	P1-68	0.0085	19	7
J-C03	0.0523	111	38	P1-69	0.0021	5	2
J-C04	0.0589	126	43	P1-70	0.0117	26	9
J-C05	0.0954	202	70	P1-71	0.0044	10	4
J-C06	0.1036	218	77	P1-72	0.0044	10	4
J-C07	0.1173	240	87	P1-73	0.003	7	3
J-C08	0.1311	266	97	P1-74	0.0105	24	9
J-C09	0.0065	15	6	P1-75	0.0067	7	1
J-C10	0.0365	76	28	P1-76	0.0089	20	7
J-C11	0.0087	20	7	P1-77	0.0087	20	7
J-C12	0.0131	30	11	P1-78	0.0087	20	7
J-C13	0.0172	39	14	P1-79	0.01	22	8
J-C14	0.021	47	17	P1-80	0.0165	37	13
J-C15	0.0213	48	18	P1-81	0.0018	4	2
J-C16	0.03	66	23	P1-82	0.008	18	7
J-C17	0.0548	120	42	P1-83	0.0174	39	14
J-C18	0.0112	25	9	P1-84	0.0115	26	10
J-C19	0.0187	42	15	P1-85	0.0066	15	6
J-C20	0.0231	50	17	P1-86	0.0143	31	11
J-C21	0.0263	54	19	P1-87	0.0082	18	7
J-C22	0.0104	23	9	P1-88	0.0137	30	11
J-C23	0.0154	33	12	P1-89	0.0138	27	10
J-C24	0.0184	37	12	P1-90	0.0038	9	3
J-C25	0.0363	73	23	P1-91	0.0017	4	1
J-C26	0.1378	242	90	P1-92	0.0044	10	4
J-C27	0.0222	49	18	P1-93	0.0041	10	4
				P1-94	0.0044	10	4
				P1-95	0.0043	10	4
				P1-96	0.0179	38	14
				P1-97	0.005	11	4
				P1-98	0.0124	28	10
				P1-99	0.0024	6	2
				P1-100	0.0046	11	4
				P1-101	0.0066	15	6
				P1-102	0.0031	7	3
				P1-103	0.0032	7	3
				P1-105	0.0073	17	6

It should be noted that the precipitation depths of the 100-yr, 6-hr event is 3-inches and that the precipitation depth of the 10-yr, 6-hr storm is 1.53-inches. The 100-yr precipitation is nearly twice for the 10-yr event. For the same events the amount of excess precipitation available for runoff is dependent on the runoff curve number, which is a function of soil type, land use, and antecedent moisture conditions. For this reason a larger portion of the 100-yr precipitation is available for runoff than for the smaller 10-yr storm and the ratio of peak runoff for the 100-yr precipitation to 10-yr precipitations is nearly 3.

GOLDEN VALLEY RANCH

All model results and input data are found in the Appendices of this study. They consist of the following:

- Appendix A – Model Results and Data provides the input parameters and results for Area 1, Phases A & B sheds.
- Appendix B – Drainage Infrastructure provides the storm drain inlet calculations open channel flow calculations through utility easements.
- Appendix C – Street Capacity Calculations
- Appendix D – Public Right-of-Way Drainage Improvements

4. Drainage Improvements within the Public Right-of-Way

Access to the project site is via Shinarump Road from the north to the new Aztec Road alignment and West Loop Road. Aztec Road will receive a culvert crossing at the Power line Easement to convey runoff from off-site areas to the Thirteen Mile Wash. The West Loop Road will have a pipe crossing from the Open Space area of Area 1, Phase 1 and convey this and other Area 1, Phases 1 & 2 runoff south, crossing a future portion of the West Loop Road and discharging into the golf course (See Figure 4). Discharge from Area 1, Phases A & B drainage sheds are discussed in Section 2.2.






Appendix D contains street capacity calculations for the arterial roads and inlet capacity calculations.

5. Comparison of Flows

The drainage shed characteristics change with development of existing lands. The pervious soils that formerly existed become less pervious with the addition of houses, streets, and sidewalks and the time for runoff to reach its release point shortens. From a drainage point of view, one of the major advantages to the adjacent golf course is that drainage runoff is routed through its fairway system. This not only allows for runoff of the major storm events, but also allows for the golf course to absorb some for the runoff volume, therefore reducing the peak flow. Figure 5 shows existing drainage as it relates to the Area 1-3 development and outside areas that will drain through the proposed system. Table 3 provides a comparison of existing flows to developed flow at major junction points. Note that while runoff from the northern release point J-N5 exceeds its existing flow into the Thirteen Mile Wash, the collective flows from J-N5 and J-S26 is less than existing due to detention provided within the golf course.

Table 3 – Flow Comparison

Shed	Area (acres)	Indirect Methods (cfs)	HEC- HMS (cfs)
J-H	73.26	191	211
J3-44	18.12	73	38
J-S5	69.79	184	187
J-S9	439.35	657	456
J-N5	369.78	582	621
J-S26	713.82	916	798



PLAN - WEST LOOP ROAD


PLAN - WEST LOOP ROAD

SHEET
6 OF 40 SHEETS
FIGURE 4
ST PROJECT
10/03/03

RHODES HOMES ARIZONA, LLC
GOLDEN VALLEY RANCH
WEST LOOP ROAD
STORM DRAIN IMPROVEMENTS
MOHAVE COUNTY ARIZONA


Stanley Consultants INC.
5820 S. Eastern Avenue, Suite 200
Las Vegas, Nevada 89119
(702) 369-3396 Fax (702) 369-9793
www.stanleygroup.com

SCALE (H) 1"=200'
SCALE (V)
DRAWN BY VND
CHECKED BY MPB
DATE 8/30/05



Stanley Consultants INC.
5620 S. EASTERN AVENUE, SUITE 200
LAS VEGAS, NEVADA 89119 (702) 369-9396

GOLDEN VALLEY RANCH
EXISTING DRAINAGE AND PROPOSED OFFSITE IMPROVEMENTS
TECHNICAL DRAINAGE STUDY EXHIBIT

ARIZONA

FIGURE 5

GOLDEN VALLEY RANCH**6. FEMA Base Flood Elevations**

The Holy Moses Diversion Wash #1 leaves the main channel east of the site. It travels in a westerly direction along the westerly sloping alluvial fan. The runoff generally remains within the washes banks, but as it reaches the channel edge it spills over into the surrounding dessert plain. Overtime the cresting and release of flow along with its sediment load has formed a channel with overbanks sloping away from the channel.

A HEC-RAS analysis provides the Base Flood Elevations (BFE) for this diversion wash. The base flood flow within Holy Moses Diversion Wash # 1 is based on derived flow from the Technical Drainage Study for Golden Valley Ranch, Mohave, Arizona, dated October 2005. Finish building grades are developed to remain 1 foot to 1.5 feet above the BFE. Figure 6 shows the BFE's for development in Areas 1-3.


7. SUMMARY

This study develops specific criteria and flow for the development of Area 1, Phases A & B.

- The majority of the development runoff can be maintained and conveyed within the street right-of-way. Where street flow capacity is reached, a storm drainage system is required.
- The drainage infrastructure is capable of conveying the 10-yr, 6-hr storm event (minimum).
- The adjacent golf course services as runoff conveyance and storage.
- Total discharge from the collective Areas 1-3 to the Thirteen Mile Wash is less because of the use of runoff volume storage provided in the golf course.
- Conveyance of stormwater runoff within the golf course fairways allows for some ground water recharge.

8. REFERENCES

- 1) *Flood Insurance Rate Map*, Community Panel Number 040058 2325 C, Mohave County, Arizona, effective October 20, 2002.
- 2) *Highway Drainage Design Manual*, Arizona Department of Transportation, Report Number FHWA-AZ93-281, Final Report, March, 1993
- 3) *Drainage Design Manual for Maricopa County, Arizona*, Hydrology: Rainfall, Flood Control District of Maricopa County, November 2003



Stanley Consultants INC.
 5820 S. EASTERN AVENUE, SUITE 200
 LAS VEGAS, NEVADA 89119 (702) 369-9396

ST-RH036320

GOLDEN VALLEY RANCH

APPENDIX A

AREA 1 – RESULTS AND DATA

- **HEC-HMS 100-YR, 6-HR SIMULATION**
- **HEC-HMS 10-YR, 6-HR SIMULATION**
- **NOAA ATLAS 14 PRECIPITATION**
- **STANDARD FORM 4**

Project: Pod1_S_curve Simulation Run: Pod1-100yr

Start of Run: 01Jan3000, 01:00 Basin Model: POD 1
 End of Run: 02Jan3000, 01:55 Meteorologic Model: S-Pattern 1(3.00IN)
 Execution Time: 15Mar2006, 11:16:57 Control Specifications: Control 1

Volume Units: AC-FT

J-C1	0.0268	56.80	01Jan3000, 05:10	2.70
J-C10	0.0365	76.41	01Jan3000, 05:10	3.67
J-C11	0.0087	19.96	01Jan3000, 05:10	0.88
J-C12	0.0131	29.74	01Jan3000, 05:10	1.32
J-C13	0.0172	38.87	01Jan3000, 05:10	1.74
J-C14	0.0210	47.29	01Jan3000, 05:10	2.13
J-C15	0.0213	47.74	01Jan3000, 05:10	2.15
J-C16	0.0300	65.79	01Jan3000, 05:10	3.02
J-C17	0.0548	120.12	01Jan3000, 05:10	5.53
J-C18	0.0112	25.05	01Jan3000, 05:10	1.13
J-C19	0.0187	41.77	01Jan3000, 05:10	1.89
J-C2	0.0341	71.23	01Jan3000, 05:10	3.44
J-C20	0.0231	49.86	01Jan3000, 05:10	2.33
J-C21	0.0263	54.45	01Jan3000, 05:10	2.65
J-C22	0.0104	23.48	01Jan3000, 05:10	1.05
J-C23	0.0154	33.04	01Jan3000, 05:10	1.56
J-C24	0.0184	37.18	01Jan3000, 05:15	1.86
J-C25	0.0363	73.15	01Jan3000, 05:10	3.67
J-C26	0.1378	241.70	01Jan3000, 05:20	13.54
J-C27	0.0222	49.42	01Jan3000, 05:10	2.24
J-C3	0.0523	111.40	01Jan3000, 05:10	5.28
J-C4	0.0589	125.94	01Jan3000, 05:10	5.95
J-C5	0.0954	202.09	01Jan3000, 05:10	9.62
J-C6	0.1036	217.95	01Jan3000, 05:10	10.45
J-C7	0.1173	240.25	01Jan3000, 05:10	11.83

J-C8	0.1311	266.40	01Jan3000, 05:15	13.22
J-C9	0.0065	14.88	01Jan3000, 05:10	0.66
P1-100	0.0046	10.53	01Jan3000, 05:10	0.46
P1-101	0.0066	14.88	01Jan3000, 05:10	0.67
P1-102	0.0031	7.30	01Jan3000, 05:05	0.31
P1-103	0.0032	7.49	01Jan3000, 05:05	0.32
P1-105	0.0073	16.51	01Jan3000, 05:10	0.74
P1-67	0.0107	24.16	01Jan3000, 05:10	1.08
P1-68	0.0085	18.57	01Jan3000, 05:10	0.86
P1-69	0.0021	4.86	01Jan3000, 05:05	0.21
P1-70	0.0117	25.64	01Jan3000, 05:10	1.18
P1-71	0.0044	10.43	01Jan3000, 05:05	0.44
P1-72	0.0044	9.97	01Jan3000, 05:10	0.44
P1-73	0.0030	6.87	01Jan3000, 05:10	0.30
P1-74	0.0105	23.50	01Jan3000, 05:10	1.06
P1-75	0.0067	6.54	01Jan3000, 05:15	0.32
P1-76	0.0089	20.03	01Jan3000, 05:10	0.90
P1-77	0.0087	19.90	01Jan3000, 05:10	0.88
P1-78	0.0087	19.58	01Jan3000, 05:10	0.88
P1-79	0.0100	22.46	01Jan3000, 05:10	1.01
P1-80	0.0165	36.62	01Jan3000, 05:10	1.66
P1-81	0.0018	4.31	01Jan3000, 05:05	0.18
P1-82	0.0080	18.00	01Jan3000, 05:10	0.81
P1-83	0.0174	38.50	01Jan3000, 05:10	1.75
P1-84	0.0115	26.06	01Jan3000, 05:10	1.16
P1-85	0.0066	15.05	01Jan3000, 05:10	0.67
P1-86	0.0143	30.58	01Jan3000, 05:10	1.44
P1-87	0.0082	17.92	01Jan3000, 05:10	0.83
P1-88	0.0137	30.41	01Jan3000, 05:10	1.38
P1-89	0.0138	26.96	01Jan3000, 05:10	1.39
P1-90	0.0038	9.11	01Jan3000, 05:05	0.38
P1-91	0.0017	4.12	01Jan3000, 05:05	0.17

P1-92	0.0044	10.24	01Jan3000, 05:05	0.44
P1-93	0.0041	9.60	01Jan3000, 05:05	0.41
P1-94	0.0044	9.85	01Jan3000, 05:10	0.44
P1-95	0.0043	10.01	01Jan3000, 05:05	0.43
P1-96	0.0179	38.28	01Jan3000, 05:10	1.80
P1-97	0.0050	11.14	01Jan3000, 05:10	0.50
P1-98	0.0124	27.71	01Jan3000, 05:10	1.25
P1-99	0.0024	5.72	01Jan3000, 05:05	0.24
R-C-11	0.0087	19.89	01Jan3000, 05:10	0.88
R-JC1	0.0268	54.71	01Jan3000, 05:10	2.71
R-JC10	0.0365	76.14	01Jan3000, 05:10	3.68
R-JC12	0.0131	29.49	01Jan3000, 05:10	1.33
R-JC13	0.0172	38.63	01Jan3000, 05:10	1.75
R-JC15	0.0213	45.89	01Jan3000, 05:10	2.15
R-JC16	0.0300	64.39	01Jan3000, 05:10	3.03
R-JC19	0.0187	39.89	01Jan3000, 05:10	1.88
R-JC2	0.0341	70.98	01Jan3000, 05:10	3.44
R-JC20	0.0231	47.13	01Jan3000, 05:10	2.33
R-JC22	0.0104	22.94	01Jan3000, 05:15	1.05
R-JC23	0.0154	32.30	01Jan3000, 05:15	1.56
R-JC24	0.0184	37.14	01Jan3000, 05:15	1.87
R-JC27	0.0222	46.16	01Jan3000, 05:15	2.23
R-JC3	0.0523	110.89	01Jan3000, 05:10	5.28
R-JC4	0.0589	125.94	01Jan3000, 05:10	5.95
R-JC5	0.0954	200.03	01Jan3000, 05:10	9.62
R-JC6	0.1036	212.89	01Jan3000, 05:15	10.45
R-JC7	0.1173	240.28	01Jan3000, 05:15	11.83
R-JC8	0.1311	236.05	01Jan3000, 05:20	13.22
R-JC9	0.0065	14.85	01Jan3000, 05:10	0.66
R-P167	0.0107	23.35	01Jan3000, 05:10	1.08
R-P169	0.0021	4.83	01Jan3000, 05:10	0.21
R-P170	0.0117	25.57	01Jan3000, 05:10	1.18

Project: Pod1_S_curve Simulation Run: Pod1-10yr

Start of Run: 01Jan3000, 01:00 Basin Model: POD 1
 End of Run: 02Jan3000, 01:55 Meteorologic Model: S-Pattern 1(1.53in)
 Execution Time: 15Mar2006, 11:17:04 Control Specifications: Control 1


Volume Units: AC-FT

Hydrologic Element	Drainage Area (MI ²)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
J-C1	0.0268	20.66	01Jan3000, 05:15	0.94
J-C10	0.0365	27.56	01Jan3000, 05:15	1.27
J-C11	0.0087	7.45	01Jan3000, 05:10	0.30
J-C12	0.0131	10.89	01Jan3000, 05:10	0.46
J-C13	0.0172	14.15	01Jan3000, 05:10	0.60
J-C14	0.0210	17.15	01Jan3000, 05:10	0.74
J-C15	0.0213	17.58	01Jan3000, 05:10	0.74
J-C16	0.0300	23.39	01Jan3000, 05:10	1.04
J-C17	0.0548	42.48	01Jan3000, 05:10	1.91
J-C18	0.0112	9.11	01Jan3000, 05:10	0.39
J-C19	0.0187	15.28	01Jan3000, 05:10	0.65
J-C2	0.0341	25.08	01Jan3000, 05:15	1.19
J-C20	0.0231	17.44	01Jan3000, 05:15	0.80
J-C21	0.0263	19.28	01Jan3000, 05:15	0.91
J-C22	0.0104	8.72	01Jan3000, 05:10	0.36
J-C23	0.0154	11.68	01Jan3000, 05:15	0.54
J-C24	0.0184	12.18	01Jan3000, 05:20	0.64
J-C25	0.0363	23.28	01Jan3000, 05:15	1.26
J-C26	0.1378	90.05	01Jan3000, 05:20	4.63
J-C27	0.0222	17.81	01Jan3000, 05:10	0.77
J-C3	0.0523	37.66	01Jan3000, 05:15	1.83
J-C4	0.0589	42.59	01Jan3000, 05:10	2.06
J-C5	0.0954	69.83	01Jan3000, 05:15	3.33
J-C6	0.1036	76.88	01Jan3000, 05:15	3.62
J-C7	0.1173	86.58	01Jan3000, 05:15	4.10

Hydrologic Element	Drainage Area (MI ²)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
J-C8	0.1311	96.50	01Jan3000, 05:15	4.58
J-C9	0.0065	5.55	01Jan3000, 05:10	0.23
P1-100	0.0046	3.95	01Jan3000, 05:10	0.16
P1-101	0.0066	5.50	01Jan3000, 05:10	0.23
P1-102	0.0031	2.68	01Jan3000, 05:10	0.11
P1-103	0.0032	2.76	01Jan3000, 05:10	0.11
P1-105	0.0073	6.12	01Jan3000, 05:10	0.25
P1-67	0.0107	8.95	01Jan3000, 05:10	0.37
P1-68	0.0085	6.76	01Jan3000, 05:10	0.30
P1-69	0.0021	1.81	01Jan3000, 05:10	0.07
P1-70	0.0117	9.35	01Jan3000, 05:10	0.41
P1-71	0.0044	3.80	01Jan3000, 05:10	0.15
P1-72	0.0044	3.70	01Jan3000, 05:10	0.15
P1-73	0.0030	2.58	01Jan3000, 05:10	0.10
P1-74	0.0105	8.65	01Jan3000, 05:10	0.37
P1-75	0.0067	1.04	01Jan3000, 05:15	0.06
P1-76	0.0089	7.40	01Jan3000, 05:10	0.31
P1-77	0.0087	7.46	01Jan3000, 05:10	0.30
P1-78	0.0087	7.23	01Jan3000, 05:10	0.30
P1-79	0.0100	8.29	01Jan3000, 05:10	0.35
P1-80	0.0165	13.42	01Jan3000, 05:10	0.57
P1-81	0.0018	1.55	01Jan3000, 05:10	0.06
P1-82	0.0080	6.65	01Jan3000, 05:10	0.28
P1-83	0.0174	14.09	01Jan3000, 05:10	0.61
P1-84	0.0115	9.67	01Jan3000, 05:10	0.40
P1-85	0.0066	5.61	01Jan3000, 05:10	0.23
P1-86	0.0143	11.05	01Jan3000, 05:10	0.50
P1-87	0.0082	6.52	01Jan3000, 05:10	0.29
P1-88	0.0137	11.15	01Jan3000, 05:10	0.48
P1-89	0.0138	9.61	01Jan3000, 05:15	0.48
P1-90	0.0038	3.28	01Jan3000, 05:10	0.13
P1-91	0.0017	1.48	01Jan3000, 05:05	0.06

Hydrologic Element	Drainage Area (MI ²)	Peak Discharge (CFS)	Time of Peak	Volume (AC-FT)
P1-92	0.0044	3.80	01Jan3000, 05:10	0.15
P1-93	0.0041	3.54	01Jan3000, 05:10	0.14
P1-94	0.0044	3.62	01Jan3000, 05:10	0.15
P1-95	0.0043	3.71	01Jan3000, 05:10	0.15
P1-96	0.0179	13.84	01Jan3000, 05:10	0.62
P1-97	0.0050	4.09	01Jan3000, 05:10	0.17
P1-98	0.0124	10.19	01Jan3000, 05:10	0.43
P1-99	0.0024	2.07	01Jan3000, 05:10	0.08
R-C-11	0.0087	7.27	01Jan3000, 05:10	0.30
R-JC1	0.0268	20.24	01Jan3000, 05:15	0.94
R-JC10	0.0365	27.50	01Jan3000, 05:15	1.27
R-JC12	0.0131	10.61	01Jan3000, 05:10	0.46
R-JC13	0.0172	13.87	01Jan3000, 05:10	0.60
R-JC15	0.0213	16.46	01Jan3000, 05:15	0.74
R-JC16	0.0300	22.28	01Jan3000, 05:15	1.05
R-JC19	0.0187	14.53	01Jan3000, 05:15	0.65
R-JC2	0.0341	25.01	01Jan3000, 05:15	1.19
R-JC20	0.0231	17.35	01Jan3000, 05:15	0.80
R-JC22	0.0104	8.26	01Jan3000, 05:15	0.36
R-JC23	0.0154	10.95	01Jan3000, 05:20	0.54
R-JC24	0.0184	12.12	01Jan3000, 05:20	0.64
R-JC27	0.0222	17.52	01Jan3000, 05:15	0.78
R-JC3	0.0523	38.03	01Jan3000, 05:15	1.83
R-JC4	0.0589	42.56	01Jan3000, 05:10	2.06
R-JC5	0.0954	71.17	01Jan3000, 05:15	3.33
R-JC6	0.1036	77.18	01Jan3000, 05:15	3.62
R-JC7	0.1173	86.89	01Jan3000, 05:15	4.10
R-JC8	0.1311	89.04	01Jan3000, 05:20	4.58
R-JC9	0.0065	5.46	01Jan3000, 05:10	0.23
R-P167	0.0107	8.46	01Jan3000, 05:15	0.37
R-P169	0.0021	1.75	01Jan3000, 05:10	0.07
R-P170	0.0117	9.30	01Jan3000, 05:10	0.41

GOLDEN VALLEY RANCH



Precipitation

Time	100-yr, 6-hr	10-yr, 6-hr
01Jan3000, 01:05	0	0
01Jan3000, 01:20	0.024	0.012
01Jan3000, 01:35	0.048	0.024
01Jan3000, 01:50	0.075	0.038
01Jan3000, 02:05	0.099	0.05
01Jan3000, 02:20	0.123	0.063
01Jan3000, 02:35	0.15	0.077
01Jan3000, 02:50	0.174	0.089
01Jan3000, 03:05	0.198	0.101
01Jan3000, 03:20	0.222	0.113
01Jan3000, 03:35	0.261	0.133
01Jan3000, 03:50	0.297	0.151
01Jan3000, 04:05	0.354	0.181
01Jan3000, 04:20	0.414	0.211
01Jan3000, 04:35	0.648	0.33
01Jan3000, 04:50	1.131	0.577
01Jan3000, 05:05	2.502	1.276
01Jan3000, 05:20	2.733	1.394
01Jan3000, 05:35	2.793	1.424
01Jan3000, 05:50	2.85	1.454
01Jan3000, 06:05	2.886	1.472
01Jan3000, 06:20	2.916	1.487
01Jan3000, 06:35	2.949	1.504
01Jan3000, 06:50	2.973	1.516
01Jan3000, 07:05	3	1.53

[illegible]

StandardForm4

SCS Curve Numbers		Curve Numbers		Sub-Basin Data		Initial/Overland Time (T _i)		Travel Time (T _t)		T _c Check		Final T _c		TLAQ		HEC-INPUT		Remarks									
Drainage Basin Name	Drainage Area (Acres)	Drainage Area (Sq. Mi.)	Cover Type and Hydrologic Condition	Curve # for Hydrologic Soils Group				Designation	K (Default by CN)	Area (Acres)	Length (feet)	Slope (%)	T _i (Min)	Length (feet)	Slope (%)	V ₁ (FPS) (Manning)	V ₂ (FPS) (Manning)	T _i (Min)	Total Length (Urbane/Basins) (feet)	T _c = T _i + T _t (Min)	T _c = T _i + T _t (Min)	Composite CN	Drainage Area (Sq. Mi.)	T _c = 10 for Non Urban			
P1-101	P1-102	P1-103	P1-105	A	B	C	D																				
				76	84	89	91	89	101	0.78	4.20	130	1.00	6.47	918	0.01	0.18	0.27	71.41	1049	15.8	15.8	9.5	89	0.0086		
				76	84	89	91	89	102	0.78	2.01	140	1.00	6.71	356	0.01	0.23	0.35	25.84	486	12.8	12.8	7.7	89	0.0031		
				76	84	89	91	89	103	0.78	2.07	140	1.00	6.71	412	0.01	0.22	0.34	30.86	552	13.1	13.1	7.8	89	0.0032		
				76	84	89	91	89	105	0.78	4.67	130	1.00	6.47	883	0.01	0.17	0.26	72.59	983	15.5	15.5	9.3	89	0.0073		
									0																		
Notes: Open space - poor 68 79 86 89 Open space - fair 49 69 79 84 Open space/parts - good 39 61 74 80 Paved (excludes right-of-way) 98 98 98 98 Paved: curbs and storm drains 98 98 98 98 Paved: open ditches (includes RW) 83 89 92 93 Gravel (includes RW) 76 85 89 91 Dirt (includes RW) 72 82 87 88 Commercial & Business 89 82 94 95 Industrial 81 88 91 93 Apartments/Condos 80 87 90 92 Townhouses/≤ 6000 sq. ft. 76 84 89 91 8000 sq. ft. lots 73 82 88 90 10,000 sq. ft. lots 61 75 83 87 14,000 sq. ft. lots 57 72 81 86 20,000 sq. ft. lots 64 70 80 85 40,000 sq. ft. lots 51 68 79 84 80,000 sq. ft. lots 46 65 77 82																											
K = 0.0132C _n -0.39 T _i = 1.87(1+K) _i L _i ^{0.12} (S _i) ^{0.13} Generalized Manning's Equations Escalating Conditions V ₁ = 14.8'(S _i /100) ^{0.5} Developed Conditions V ₁ = 20.2'(S _i /100) ^{0.5} V ₂ = 29.4'(S _i /100) ^{0.5} V ₂ = 30.8'(S _i /100) ^{0.5}																											

18449 - POD 1
 HEC-HMS DATA RESULTS
 C:\temp\20061603\18476P1StdForm4.xls

ST-RH036331

Shed Parameters - Pod 1

DEVELOPED CONDITIONS					
Drainage Shed	Area (ac)	Elev dn	Elev up	Length (ft)	Slope
P1- 67	6.82056208	2528.9	2522.9	887	0.6764%
P1- 68	5.43982051	2525.4	2516.7	1232	0.7062%
P1- 69	1.33282528	2525.3	2520.4	468	1.0470%
P1- 70	7.47393562	2525.4	2513.3	1240	0.9758%
P1- 71	2.78410071	2520.9	2517.4	318	1.1006%
P1- 72	2.82990899	2503.1	2497.6	817	0.6732%
P1- 73	1.94640098	2497.6	2492.4	569	0.9139%
P1- 74	6.72332983	2498.9	2488.7	1038	0.9827%
P1- 75	4.28184465	2517.4	2489.2	2240	1.2589%
P1- 76	5.70996719	2502.2	2497.3	925	0.5297%
P1- 77	5.54738366	2499.8	2493.2	602	1.0963%
P1- 78	5.57736688	2509.5	2503.9	941	0.5951%
P1- 79	6.42571205	2512.2	2503.9	990	0.8384%
P1- 80	10.5553556	2530.2	2520.8	1144	0.8217%
P1- 81	1.17969603	2518.9	2515	286	1.3636%
P1- 82	5.12524784	2518.9	2506.1	952	1.3445%
P1- 83	11.151259	2519.5	2510.4	1186	0.7673%
P1- 84	7.38699887	2524.7	2517.8	821	0.8404%
P1- 85	4.23359978	2518.1	2510.9	726	0.9917%
P1- 86	9.13315676	2524.1	2507.5	1474	1.1262%
P1- 87	5.24655358	2519.5	2505.4	1294	1.0896%
P1- 88	8.75517188	2512.4	2502.4	1147	0.8718%
P1- 89	8.803328	2518.7	2496.9	2026	1.0760%
P1- 90	2.41032003	2502.3	2499.3	290	1.0345%
P1- 91	1.08501801	2514.2	2510	231	1.8182%
P1- 92	2.80949645	2508.4	2505.3	436	0.7110%
P1- 93	2.64865483	2502.7	2500.5	400	0.5500%
P1- 94	2.81184315	2503.1	2497.3	1054	0.5503%
P1- 95	2.72709787	2506.4	2503.1	430	0.7674%
P1- 96	11.4479667	2508.2	2489.6	1459	1.2748%
P1- 97	3.21621621	2508.9	2497.6	1103	1.0245%
P1- 98	7.95973724	2551.1	2497.3	1054	5.1044%
P1- 99	1.53009463	2513.9	2507.9	304	1.9737%
P1- 100	2.96143496	2494.8	2488.7	550	1.1091%
P1- 101	4.20201393	2498.1	2490.7	919	0.8052%
P1- 102	2.01486774	2495.7	2491.1	356	1.2921%
P1- 103	2.06835346	2495.6	2490.6	412	1.2136%
P1- 105	4.66530826	2519.1	2513	863	0.7068%

Routing

Kinematic Routing

Reach	Length (ft)	slope	Manning "n"	Sub reaches	Shape	Width	Side Slope (xH:V)
R-C-11	250	0.007	0.016	5	Trapezoid	60	0.5
R-JC1	530	0.01	0.016	5	Trapezoid	20	0.5
R-JC10	50	0.01	0.016	5	Trapezoid	20	0.5
R-JC12	170	0.007	0.016	5	Trapezoid	60	0.5
R-JC13	150	0.007	0.016	5	Trapezoid	60	0.5
R-JC15	820	0.007	0.016	5	Trapezoid	60	0.5
R-JC16	330	0.007	0.016	5	Trapezoid	60	0.5
R-JC19	830	0.007	0.016	5	Trapezoid	60	0.5
R-JC2	50	0.01	0.016	5	Trapezoid	20	0.5
R-JC20	680	0.0109	0.016	5	Trapezoid	60	0.5
R-JC22	1000	0.01	0.025	5	Trapezoid	100	0
R-JC23	550	0.008	0.016	5	Trapezoid	60	0.5
R-JC24	390	0.009	0.016	5	Trapezoid	60	0.5
R-JC27	1130	0.007	0.016	5	Trapezoid	60	0.5
R-JC9	200	0.01	0.023	5	Trapezoid	20	0.5
RP1101	400	0.007	0.016	5	Trapezoid	60	0.5
RP1102	380	0.007	0.016	5	Trapezoid	60	0.5
R-P167	650	0.005	0.016	5	Trapezoid	60	0.5
R-P169	330	0.01	0.025	5	Trapezoid	50	0.5
R-P170	50	0.01	0.016	5	Trapezoid	20	0.5
R-P179	200	0.007	0.016	5	Trapezoid	60	0.5
R-P180	1140	0.007	0.016	5	Trapezoid	60	0.5
R-P181	730	0.007	0.016	5	Trapezoid	60	0.5
R-P192	250	0.007	0.016	5	Trapezoid	60	0.5

Modified Puls Routing

Reach	Paired Data Table*
R-JC3	R-JC3
R-JC4	R-JC4
R-JC5	R-JC5
R-JC6	R-JC6
R-JC7	R-JC7
R-JC8	R-JC8

* See OpenSpace_upper-Mod Puls worksheet for data

OpenSpace_upper-Mod Puls

F-JC8		R-J7		R-J6	R-J5	R-J4	R-J3
Flow	sta450-0	Flow	sta250-0	sta600-250	sta900-600	sta1200-900	1350-1200
(cfs)	Storage (ac-ft)	(cfs)	Storage (ac-ft)	Storage (ac-ft)	Storage (ac-ft)	Storage (ac-ft)	Storage (ac-ft)
25	0.0851	25	0.0360	0.0547	0.0509	0.0008	0.0259
50	0.1633	50	0.0603	0.0897	0.0867	0.0014	0.0437
75	0.2662	75	0.0817	0.1219	0.1177	0.0019	0.0592
100	0.4082	100	0.1013	0.1520	0.1422	0.0025	0.0733
125	0.5713	125	0.1199	0.1804	0.1721	0.0030	0.0861
150	0.7372	150	0.1378	0.2073	0.1958	0.0034	0.0978
200	1.1608	175	0.1546	0.2336	0.2182	0.0039	0.1088
250	1.6430	200	0.1712	0.2704	0.2402	0.0043	0.1195
300	2.2029	250	0.2020	0.3228	0.2825	0.0051	0.1392



POINT PRECIPITATION FREQUENCY ESTIMATES FROM NOAA ATLAS 14



Arizona 35.14 N 114.18 W 2703 feet

from "Precipitation-Frequency Atlas of the United States" NOAA Atlas 14, Volume 1, Version 3

G.M. Bonnin, D. Todd, B. Lin, T. Parzybok, M. Yekta, and D. Riley

NOAA, National Weather Service, Silver Spring, Maryland, 2003

Extracted: Tue Mar 14 2006


Confidence Limits	Seasonality	Location Maps	Other Info	GIS data	Maps	Help	D
-------------------	-------------	---------------	------------	----------	------	------	---

Precipitation Frequency Estimates (inches)																		
ARI* (years)	5 min	10 min	15 min	30 min	60 min	120 min	3 hr	6 hr	12 hr	24 hr	48 hr	4 day	7 day	10 day	20 day	30 day	45 day	60 day
2	0.23	0.35	0.43	0.58	0.72	0.82	0.89	1.04	1.22	1.51	1.75	1.91	2.18	2.36	2.87	3.40	3.95	4.46
5	0.33	0.50	0.62	0.83	1.03	1.17	1.25	1.44	1.68	2.08	2.40	2.60	2.96	3.23	3.96	4.69	5.51	6.24
10	0.40	0.61	0.75	1.01	1.25	1.44	1.53	1.76	2.05	2.53	2.90	3.13	3.55	3.90	4.77	5.64	6.64	7.53
25	0.49	0.75	0.93	1.26	1.55	1.82	1.95	2.22	2.56	3.15	3.61	3.85	4.36	4.81	5.85	6.89	8.14	9.25
50	0.57	0.86	1.07	1.44	1.78	2.12	2.29	2.59	2.97	3.66	4.17	4.42	4.98	5.53	6.70	7.83	9.29	10.54
100	0.65	0.98	1.22	1.64	2.03	2.44	2.67	3.00	3.42	4.19	4.76	5.01	5.62	6.26	7.56	8.78	10.45	11.86
200	0.73	1.10	1.37	1.84	2.28	2.79	3.07	3.44	3.88	4.75	5.39	5.64	6.29	7.03	8.44	9.73	11.62	13.19
500	0.84	1.27	1.58	2.12	2.63	3.27	3.67	4.08	4.55	5.55	6.26	6.50	7.21	8.12	9.64	10.99	13.18	14.96
1000	0.93	1.41	1.75	2.36	2.92	3.68	4.17	4.62	5.10	6.20	6.97	7.19	7.95	8.98	10.56	11.95	14.37	16.33

Text version of table


* These precipitation frequency estimates are based on a partial duration series. ARI is the Average Recurrence Interval. Please refer to the documentation for more information. NOTE: Formatting forces estimates near zero to appear as zero.

Partial duration based Point Precipitation Frequency Estimates Version: 3
35.14 N 114.18 W 2703 ft



Duration			
5-min —	120-min —	48-hr —	30-day —
10-min —	3-hr —	4-day —	45-day —
15-min —	6-hr —	7-day —	60-day —
30-min —	12-hr —	10-day —	
60-min —	24-hr —	20-day —	

Partial duration based Point Precipitation Frequency Estimates Version: 3
35.14 N 114.18 W 2703 ft



Average Recurrence Interval (years)	
2	+
5	+
10	+
25	+
50	+
100	+
200	+
500	+
1000	+

Confidence Limits -

* Upper bound of the 90% confidence interval Precipitation Frequency Estimates (inches)																		
ARI** (years)	5 min	10 min	15 min	30 min	60 min	120 min	3 hr	6 hr	12 hr	24 hr	48 hr	4 day	7 day	10 day	20 day	30 day	45 day	60 day
2	0.27	0.42	0.52	0.70	0.86	1.00	1.06	1.23	1.40	1.72	1.97	2.15	2.46	2.65	3.22	3.83	4.49	5.12
5	0.39	0.60	0.74	0.99	1.23	1.42	1.48	1.69	1.93	2.36	2.70	2.92	3.33	3.62	4.43	5.29	6.26	7.16
10	0.48	0.73	0.90	1.21	1.50	1.75	1.83	2.07	2.35	2.86	3.27	3.52	4.00	4.37	5.34	6.35	7.56	8.65
25	0.59	0.90	1.11	1.50	1.85	2.20	2.31	2.60	2.94	3.57	4.07	4.33	4.90	5.40	6.57	7.75	9.28	10.64
50	0.68	1.03	1.28	1.72	2.13	2.58	2.72	3.05	3.43	4.15	4.72	4.98	5.61	6.21	7.53	8.84	10.61	12.13
100	0.77	1.18	1.46	1.96	2.43	2.98	3.18	3.57	3.98	4.79	5.41	5.68	6.36	7.08	8.54	9.96	11.97	13.71
200	0.87	1.33	1.65	2.22	2.75	3.42	3.73	4.13	4.58	5.46	6.15	6.43	7.17	8.01	9.57	11.09	13.36	15.33
500	1.02	1.56	1.93	2.60	3.22	4.09	4.53	4.99	5.52	6.46	7.22	7.49	8.30	9.33	10.99	12.61	15.24	17.51
1000	1.15	1.75	2.17	2.93	3.62	4.67	5.22	5.73	6.32	7.30	8.10	8.35	9.21	10.40	12.13	13.82	16.75	19.23

* The upper bound of the confidence interval at 90% confidence level is the value which 5% of the simulated quantile values for a given frequency are greater than.

** These precipitation frequency estimates are based on a partial duration series. ARI is the Average Recurrence Interval.

Please refer to the documentation for more information. NOTE: Formatting prevents estimates near zero to appear as zero.

* Lower bound of the 90% confidence interval Precipitation Frequency Estimates (inches)																		
--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--



ARI** (years)	5 min	10 min	15 min	30 min	60 min	120 min	3 hr	6 hr	12 hr	24 hr	48 hr	4 day	7 day	10 day	20 day	30 day	45 day	60 day
2	0.19	0.29	0.36	0.49	0.60	0.69	0.76	0.91	1.06	1.34	1.55	1.71	1.95	2.10	2.56	3.01	3.45	3.87
5	0.28	0.42	0.52	0.70	0.87	0.98	1.06	1.25	1.45	1.84	2.12	2.31	2.64	2.87	3.52	4.15	4.80	5.40
10	0.33	0.51	0.63	0.85	1.05	1.19	1.29	1.51	1.77	2.23	2.56	2.79	3.16	3.46	4.22	4.98	5.78	6.50
25	0.41	0.62	0.78	1.04	1.29	1.47	1.60	1.86	2.16	2.74	3.16	3.40	3.85	4.25	5.14	6.07	7.05	7.96
50	0.46	0.70	0.87	1.18	1.46	1.70	1.86	2.13	2.46	3.14	3.62	3.88	4.37	4.85	5.86	6.85	7.99	9.02
100	0.52	0.79	0.98	1.32	1.63	1.92	2.12	2.41	2.77	3.55	4.10	4.37	4.91	5.46	6.58	7.64	8.92	10.07
200	0.57	0.87	1.08	1.46	1.80	2.14	2.37	2.70	3.08	3.96	4.58	4.86	5.43	6.07	7.29	8.41	9.86	11.13
500	0.65	0.98	1.22	1.64	2.03	2.46	2.74	3.08	3.48	4.52	5.25	5.52	6.14	6.91	8.23	9.40	11.06	12.46
1000	0.70	1.06	1.32	1.78	2.20	2.68	3.03	3.38	3.80	4.94	5.76	6.03	6.69	7.57	8.92	10.12	11.96	13.46

* The lower bound of the confidence interval at 90% confidence level is the value which 5% of the simulated quantile values for a given frequency are less than.

** These precipitation frequency estimates are based on a partial duration maxima series. ARI is the Average Recurrence Interval.

Please refer to the [documentation](#) for more information. NOTE: Formatting prevents estimates near zero to appear as zero.

Maps -



These maps were produced using a direct map request from the U.S. Census Bureau Mapping and Cartographic Resources Tiger Map Server.


Please read [disclaimer](#) for more information.

LEGEND

- State
- County
- Indian Resv
- Lake/Pond/Ocean
- Street
- Expressway
- Highway
- Connector
- Stream
- Military Area
- National Park
- Other Park
- City
- County

Scale 1:228583

*average--true scale depends on monitor resolution



Other Maps/Photographs -

View USGS digital orthophoto quadrangle (DOQ) covering this location from TerraServer; **USGS Aerial Photograph** may also be available from this site. A DOQ is a computer-generated image of an aerial photograph in which image displacement caused by terrain relief and camera tilts has been removed. It combines the image characteristics of a photograph with the geometric qualities of a map. Visit the [National Digital Orthophoto Program \(NDOP\)](#) for more information.

Watershed/Stream Flow Information -

[Find the Watershed](#) for this location using the U.S. Environmental Protection Agency's site.

Climate Data Sources -

Precipitation frequency results are based on data from a variety of sources, but largely NCDC. The following links provide general information about observing sites in the area, regardless of if their data was used in this study. For detailed information about the stations used in this study, please refer to our documentation.

Using the [National Climatic Data Center's \(NCDC\)](#) station search engine, locate other climate stations within:

...OR... of this location (35.14/-114.18). Digital ASCII data can be obtained directly from [NCDC](#).

Find Natural Resources Conservation Service (NRCS) SNOTEL (SNOWpack TELemetry) stations by visiting the [Western Regional Climate Center's state-specific SNOTEL station maps](#).

Hydrometeorological Design Studies Center
DOC/NOAA/National Weather Service
1325 East-West Highway
Silver Spring, MD 20910
(301) 713-1669
Questions?: HDSC.Questions@noaa.gov


[Disclaimer](#)

GOLDEN VALLEY RANCH

APPENDIX B

DRAINAGE INFRASTRUCTURE CALCULATIONS

- **COMMON LOT O (P1-83)**
- **COMMON LOT F (J-C14)**
- **COMMON LOT E (J-C17)**
- **H STREET (J-C21)**
- **COMMON LOT D (J-C25)**

					 Stanley Consultants INC.			
REVISIONS	DWN	APVD	APVD	DATE				
DESIGNED RJM		RHODES HOMES ARIZONA GOLDEN VALLEY RANCH AREA 1 - PHASE A			COMMON LOT 0 SHED P1-83		SCALE 1" = 30'	
DRAWN RJM							NO.	REV.
CHECKED								
APPROVED								
APPROVED								
DATE 3/02/06		A		0				

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Sag
Date: 03/10/2006Project No. :18449
Project Name.:GOLDEN VALLEY RANCH
Computed by :rjm

Project Description
 SAG INLETS - ALL PODS
 MODIFIED "C" L-17.5
 SHERO P1-83 INLET A Common Lot. "G"
 Inlets on Sag: Sweeper Combination Inlet

Roadway and Discharge Data

	Cross Slope	Composite/Dep
Sx	Pavement Cross Slope (ft/ft)	0.0100
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00

Inlet Interception

	Inlet Type *Sag*	Curb-Opening
L	Curb-Opening Length (ft)	8.75
H	Curb-Opening Height (in)	6.00
	Inlet Type *Sag*	Parallel Bar P-1-7/8
T	Width of Spread (ft)	39.00
WGR	Grate Width (ft)	1.50
L	Grate Length (ft)	7.38
	Inlet Type *Sag*	Sweeper Combination
d_ave	Depth of Flow (ft)	0.521
d_curb	Depth at Curb (ft)	0.667
Qi	Intercepted Flow (cfs)	15.000

Note: The curb opening length in the input screen is the total of the curb opening including its length along the grate.

Worksheet**Worksheet for Triangular Channel****Project Description**

Worksheet	COMMON LOT G - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Input Data

Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	24.00 cfs

Results

Depth	0.60 ft
Flow Area	10.2 ft ²
Wetted Perimeter	34.36 ft
Top Width	34.34 ft
Critical Depth	0.53 ft
Critical Slope	0.009063 ft/ft
Velocity	2.34 ft/s
Velocity Head	0.09 ft
Specific Energy	0.68 ft
Froude Number	0.76
Flow Type	Subcritical


VELOCITY x DEPTH.


$$2.3 \times 0.6 = 1.4 < 6.0$$

Cross Section
Cross Section for Triangular Channel

Project Description	
Worksheet	COMMON LOT G - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Depth	0.60 ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	24.00 cfs





Q:\18449\dwg\design\SD_PRO\POD1\POD1_Jstr_CULDESAC.dwg, 3/16/2006 5:45:52 PM, \\vg-ps1\hp5100-eng, 1:1

\$\$\$\$\$FILENAME\$\$\$\$\$

CADD A1-R3 © STANLEY CONSULTANTS

REVISIONS	DWN	APVD	APVD	DATE
DESIGNED RJM				
DRAWN RN				
CHECKED				
APPROVED				
APPROVED				
DATE DATE				



RHODES HOMES ARIZONA
GOLDEN VALLEY RANCH
AREA 1 - PHASE A

COMMON LOT 0
SHED P1-83

SCALE

NO.

A

REV.

0

ST-RH036345

F 0 5 1 5 P

PAGE NO 3

WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS -

GOLDEN VALLEY RANCH

HEADING LINE NO 2 IS -

GOLDEN VALLEY

HEADING LINE NO 3 IS -

EASEMENT DETAIL J STREET TO GOLF COURSE - 15CFS - P183

ST-RH036346

DATE: 3/14/2006
TIME: 13:45

F0515P
WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING

PAGE 1

CARD	SECT	CHN	NO OF	AVE PIER	HEIGHT 1	BASE	ZL	ZR	INV	Y(1)	Y(2)	Y(3)	Y(4)	Y(5)	Y(6)	Y(7)	Y(8)	Y(9)	Y(10)
CODE	NO	TYPE	PIERS	WIDTH	DIAMETER	WIDTH			DROP										
CD	24	4				2.00													

F 0 5 1 5 P

PAGE NO 2

WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	1	IS A SYSTEM OUTLET	*	*	*
		U/S DATA	STATION	INVERT	SECT
			100.00	2500.00	24

W S ELEV
2504.20

ELEMENT NO	2 IS A REACH	*	*	*
	U/S DATA	STATION	INVERT	SECT
		265.00	2505.91	24

N
0.013

RADIUS	ANGLE	ANG PT	MAN H
0.00	0.00	0.00	0

ELEMENT NO	3 IS A SYSTEM HEADWORKS			*
	U/S DATA	STATION	INVERT	SECT
		265.00	2505.91	24

```

W S ELEV
      0.00

```

NO EDIT ERRORS ENCOUNTERED-COMPUTATION IS NOW BEGINNING

** WARNING NO. 2 ** - WATER SURFACE ELEVATION GIVEN IS LESS THAN OR EQUALS INVERT ELEVATION IN HDWKDS, W.S.ELEV = INV + DC

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 1

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
EASEMENT DETAIL Y J STREET TO GOLF COURSE

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SP AVE	HF			NORM DEPTH			ZR	
100.00	2500.00	4.200	2504.200	15.0	4.77	0.354	2504.554	0.00	1.396	2.00	0.00	0.00	0	0.00
63.12	0.03582					.004396	0.28			0.820		0.00		
163.12	2502.26	2.220	2504.481	15.0	4.77	0.354	2504.835	0.00	1.396	2.00	0.00	0.00	0	0.00
HYDRAULIC JUMP														0.00
163.12	2502.26	0.843	2503.104	15.0	11.92	2.208	2505.312	0.00	1.396	2.00	0.00	0.00	0	0.00
18.65	0.03582					.031962	0.60			0.820		0.00		
181.77	2502.93	0.843	2503.772	15.0	11.91	2.204	2505.976	0.00	1.396	2.00	0.00	0.00	0	0.00
28.97	0.03582					.029974	0.87			0.820		0.00		
210.74	2503.97	0.874	2504.840	15.0	11.36	2.002	2506.842	0.00	1.396	2.00	0.00	0.00	0	0.00
15.73	0.03582					.026343	0.41			0.820		0.00		
226.47	2504.53	0.907	2505.437	15.0	10.83	1.821	2507.258	0.00	1.396	2.00	0.00	0.00	0	0.00
10.47	0.03582					.023157	0.24			0.820		0.00		
236.94	2504.91	0.940	2505.845	15.0	10.32	1.655	2507.500	0.00	1.396	2.00	0.00	0.00	0	0.00
7.41	0.03582					.020366	0.15			0.820		0.00		
244.35	2505.17	0.976	2506.146	15.0	9.84	1.504	2507.650	0.00	1.396	2.00	0.00	0.00	0	0.00
5.58	0.03582					.017930	0.10			0.820		0.00		
249.93	2505.37	1.013	2506.383	15.0	9.39	1.368	2507.751	0.00	1.396	2.00	0.00	0.00	0	0.00
4.26	0.03582					.015793	0.07			0.820		0.00		
254.19	2505.52	1.052	2506.575	15.0	8.95	1.244	2507.819	0.00	1.396	2.00	0.00	0.00	0	0.00
3.29	0.03582					.013924	0.05			0.820		0.00		
257.48	2505.64	1.093	2506.734	15.0	8.53	1.130	2507.864	0.00	1.396	2.00	0.00	0.00	0	0.00
2.54	0.03582					.012286	0.03			0.820		0.00		

ST-RH036349

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 2

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
EASEMENT DETAIL Y J STREET TO GOLF COURSE

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SF AVE	HF			NORM DEPTH			ZR	
260.02	2505.73	1.136	2506.868	15.0	8.13	1.027	2507.895	0.00	1.396	2.00	0.00	0.00	0	0.00
1.90	0.03582					.010856	0.02			0.820		0.00		
261.92	2505.80	1.182	2506.982	15.0	7.76	0.934	2507.916	0.00	1.396	2.00	0.00	0.00	0	0.00
1.41	0.03582					.009604	0.01			0.820		0.00		
263.33	2505.85	1.230	2507.080	15.0	7.40	0.849	2507.929	0.00	1.396	2.00	0.00	0.00	0	0.00
0.96	0.03582					.008507	0.01			0.820		0.00		
264.29	2505.89	1.281	2507.166	15.0	7.05	0.772	2507.938	0.00	1.396	2.00	0.00	0.00	0	0.00
0.54	0.03582					.007550	0.00			0.820		0.00		
264.83	2505.90	1.336	2507.240	15.0	6.72	0.702	2507.942	0.00	1.396	2.00	0.00	0.00	0	0.00
0.17	0.03582					.006712	0.00			0.820		0.00		
265.00	2505.91	1.396	2507.306	15.0	6.40	0.637	2507.943	0.00	1.396	2.00	0.00	0.00	0	0.00

ST-RH036350

GOLDEN VALLEY RANCH
GOLDEN VALLEY
EASEMENT DETAIL Y J STREET TO GOLF COURSE


[illegible]

NOTES

1. GLOSSARY

I = INVERT ELEVATION
 C = CRITICAL DEPTH
 W = WATER SURFACE ELEVATION
 H = HEIGHT OF CHANNEL
 E = ENERGY GRADE LINE
 X = CURVES CROSSING OVER
 B = BRIDGE ENTRANCE OR EXIT
 Y = WALL, ENTRANCE OR EXIT

2. STATIONS FOR POINTS AT A JUMP MAY NOT BE PLOTTED EXACTLY



STORM DRAIN SYSTEM					
INLET	SIZE	Qinlet	Qintercept	Qbypass	Grade/Sump
A	8.5	19	7	9	G
B	11.5	20	10	10	G
C	11.5	28	11	17	S

SD PIPES		
PIPE	Qpipe	Size
1	19	30

REVISIONS	OWN	APVD	APVD	DATE



DESIGNED RJM
DRAWN RJM
CHECKED _____
APPROVED _____
APPROVED _____
DATE 3/02/06

RHOES HOMES ARIZONA
GOLDEN VALLEY RANCH
AREA 1 - PHASE A

COMMON LOT F
NODE J-C14

SCALE 1" = 40'

NO.

A

REV.

0

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway Pavements

Inlets on Grade
Date: 03/15/2006

Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT F
NODE J-C14
INLET A

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0063
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	19.000
T	Width of Spread (ft)	23.45

Gutter Flow

Eo	Gutter Flow Ratio	0.186
d	Depth of Flow (ft)	0.56
V	Average Velocity (ft/sec)	3.41

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	31.70	4.25	0.08	1.453	17.547
Parallel Bar P-1-7/8	1.50	2.88	0.31	5.456	12.092
Combination			0.36	6.908	12.092

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway Pavements

Inlets on Grade
Date: 03/15/2006

Project No. :18476 - Pod 1
Project Name.:GOLDEN VALLEY RANCH
Computed by :rjm

Project Description

LOT F
NODE J-C14
INLET B

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0051
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	20.000
T	Width of Spread (ft)	25.00

Gutter Flow

Eo	Gutter Flow Ratio	0.174
d	Depth of Flow (ft)	0.59
V	Average Velocity (ft/sec)	3.17

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	31.15	5.75	0.08	1.555	18.445
Parallel Bar P-1-7/8	1.50	4.38	0.46	8.482	9.963
Combination			0.50	10.037	9.963

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Sag
Date: 03/10/2006Project No. :18449
Project Name.:GOLDEN VALLEY RANCH
Computed by :rjm

Project Description

SAG INLETS - ALL PODS

MODIFIED "C" L-11.5

PODS J-C14 INLET C

Inlets on Sag: Sweeper Combination Inlet

Roadway and Discharge Data

	Cross Slope	Composite/Dep
Sx	Pavement Cross Slope (ft/ft)	0.0100
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00

Inlet Interception

	Inlet Type *Sag*	Curb-Opening
L	Curb-Opening Length (ft)	5.75
H	Curb-Opening Height (in)	6.00
	Inlet Type *Sag*	Parallel Bar P-1-7/8
T	Width of Spread (ft)	39.48
WGR	Grate Width (ft)	1.50
L	Grate Length (ft)	4.38
	Inlet Type *Sag*	Sweeper Combination
d_ave	Depth of Flow (ft)	0.526
d_curb	Depth at Curb (ft)	0.671
Qi	Intercepted Flow (cfs)	11.000

Note: The curb opening length in the input screen is the total of the curb opening including its length along the grate.

Worksheet

Worksheet for Triangular Channel

Project Description	
Worksheet	COMMON LOT F - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Input Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	19.00 cfs

Results	
Depth	0.55 ft
Flow Area	8.6 ft ²
Wetted Perimeter	31.49 ft
Top Width	31.47 ft
Critical Depth	0.49 ft
Critical Slope	0.009350 ft/ft
Velocity	2.21 ft/s
Velocity Head	0.08 ft
Specific Energy	0.62 ft
Froude Number	0.75
Flow Type	Subcritical

VELOCITY x DEPTH


$$2.2 \times 0.6 = 1.3 < 6.0$$

Cross Section

Cross Section for Triangular Channel

Project Description	
Worksheet	COMMON LOT F - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth



Section Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Depth	0.55 ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	19.00 cfs



Q:\18449\dwg\design\SD_PRO\POD1\WLR_STA105+85.dwg, 3/16/2006 5:53:01 PM, \\vg-ps1\hp5100-eng, 1:1

\$\$\$\$\$FILENAME\$\$\$\$\$

CADD AT-R3 © STANLEY CONSULTANTS



HS 1" = 100'
VS 1" = 10'

LEGEND	
---	Existing Grade
---	Finish Grade
---	HGL

REVISIONS	DWN	APVD	APVD	DATE
DESIGNED RJM				
DRAWN RN				
CHECKED				
APPROVED				
DATE DATE				



RHODES HOMES ARIZONA
GOLDEN VALLEY RANCH
AREA 1 - PHASE A

COMMON LOT F
NODE J-C14

SCALE	
NO.	REV.
A	0

F 0 5 1 5 P

PAGE NO 3

WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS -

GOLDEN VALLEY RANCH

HEADING LINE NO 2 IS -

GOLDEN VALLEY

HEADING LINE NO 3 IS -

LATERAL WITH JC14 - 28 CFS

ST-RH036359

F 0 5 1 5 P

PAGE NO 3

WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS -

GOLDEN VALLEY RANCH

HEADING LINE NO 2 IS -

GOLDEN VALLEY

HEADING LINE NO 3 IS -

LATERAL WITH JCL4 - 28 CFS AT STA 105 + ON WLPR

ST-RH036360

F 0 5 1 5 P

PAGE NO 2

WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	1 IS A SYSTEM OUTLET	U/S DATA	STATION	INVERT	SECT	W S ELEV								
			100.00	2482.64	30	2490.18								
ELEMENT NO	2 IS A REACH	U/S DATA	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H				
			240.00	2483.34	30	0.013	0.00	0.00	0.00	0				
ELEMENT NO	3 IS A JUNCTION	U/S DATA	STATION	INVERT	SECT	LAT-1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4
			245.00	2483.36	30	0	0	0.014	0.0	0.0	0.00	0.00	0.00	0.00
ELEMENT NO	4 IS A REACH	U/S DATA	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H				
			372.00	2484.00	30	0.013	0.00	0.00	5.00	0				
ELEMENT NO	5 IS A JUNCTION	U/S DATA	STATION	INVERT	SECT	LAT-1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4
			377.00	2484.02	30	0	0	0.014	0.0	0.0	0.00	0.00	0.00	0.00
ELEMENT NO	6 IS A REACH	U/S DATA	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H				
			502.00	2484.65	30	0.013	0.00	0.00	5.00	0				
ELEMENT NO	7 IS A JUNCTION	U/S DATA	STATION	INVERT	SECT	LAT-1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4
			507.00	2484.67	30	0	0	0.014	0.0	0.0	0.00	0.00	0.00	0.00
ELEMENT NO	8 IS A REACH	U/S DATA	STATION	INVERT	SECT	N	RADIUS	ANGLE	ANG PT	MAN H				
			715.00	2494.47	30	0.013	0.00	0.00	70.00	0				
ELEMENT NO	9 IS A SYSTEM HEADWORKS	U/S DATA	STATION	INVERT	SECT	W S ELEV								
			715.00	2494.47	30	0.00								

NO EDIT ERRORS ENCOUNTERED-COMPUTATION IS NOW BEGINNING

** WARNING NO. 2 ** - WATER SURFACE ELEVATION GIVEN IS LESS THAN OR EQUALS INVERT ELEVATION IN HDWKDS, W-S.ELEV = INV + DC

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 1

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH JC14 - 28 CFS

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.EV.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SF AVE	HF			NORM DEPTH		ZR		
100.00	2482.64	7.540	2490.180	28.0	5.70	0.505	2490.685	0.00	1.804	2.50	0.00	0.00	0	0.00
140.00	0.00500					.004660	0.65			1.973		0.00		
240.00	2483.34	7.492	2490.832	28.0	5.70	0.505	2491.337	0.00	1.804	2.50	0.00	0.00	0	0.00
JUNCT STR	0.00400					.005404	0.03					0.00		
245.00	2483.36	7.499	2490.859	28.0	5.70	0.505	2491.364	0.00	1.804	2.50	0.00	0.00	0	0.00
127.00	0.00504					.004660	0.59			1.970		0.00		
372.00	2484.00	7.460	2491.460	28.0	5.70	0.505	2491.965	0.00	1.804	2.50	0.00	0.00	0	0.00
JUNCT STR	0.00400					.005404	0.03					0.00		
377.00	2484.02	7.467	2491.487	28.0	5.70	0.505	2491.992	0.00	1.804	2.50	0.00	0.00	0	0.00
125.00	0.00504					.004660	0.58			1.970		0.00		
502.00	2484.65	7.427	2492.077	28.0	5.70	0.505	2492.582	0.00	1.804	2.50	0.00	0.00	0	0.00
JUNCT STR	0.00400					.005404	0.03					0.00		
507.00	2484.67	7.434	2492.104	28.0	5.70	0.505	2492.609	0.00	1.804	2.50	0.00	0.00	0	0.00
104.95	0.04711					.004660	0.49			0.961		0.00		
611.95	2489.61	3.082	2492.697	28.0	5.70	0.505	2493.202	0.00	1.804	2.50	0.00	0.00	0	0.00
HYDRAULIC JUMP												0.00		
611.95	2489.61	1.008	2490.623	28.0	15.11	3.546	2494.169	0.00	1.804	2.50	0.00	0.00	0	0.00
4.09	0.04711					.039811	0.16			0.961		0.00		
616.04	2489.81	1.008	2490.815	28.0	15.09	3.538	2494.353	0.00	1.804	2.50	0.00	0.00	0	0.00
29.13	0.04711					.037340	1.09			0.961		0.00		
645.17	2491.18	1.045	2492.225	28.0	14.40	3.218	2495.443	0.00	1.804	2.50	0.00	0.00	0	0.00
17.77	0.04711					.032787	0.58			0.961		0.00		

ST-RH036362

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 2

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH JC14 - 28 CFS

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD. EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVEPR
L/ELEM	SO					SF AVE	HF			NORM DEPTH		ZR		
662.94	2492.02	1.083	2493.100	28.0	13.73	2.925	2496.025	0.00	1.804	2.50	0.00	0.00	0	0.00
12.33	0.04711					.028800	0.36			0.961		0.00		
675.27	2492.60	1.123	2493.721	28.0	13.08	2.658	2496.379	0.00	1.804	2.50	0.00	0.00	0	0.00
9.17	0.04711					.025315	0.23			0.961		0.00		
684.44	2493.03	1.165	2494.195	28.0	12.48	2.418	2496.613	0.00	1.804	2.50	0.00	0.00	0	0.00
7.07	0.04711					.022267	0.16			0.961		0.00		
691.51	2493.36	1.209	2494.572	28.0	11.89	2.197	2496.769	0.00	1.804	2.50	0.00	0.00	0	0.00
5.59	0.04711					.019599	0.11			0.961		0.00		
697.10	2493.63	1.255	2494.882	28.0	11.35	1.999	2496.881	0.00	1.804	2.50	0.00	0.00	0	0.00
4.48	0.04711					.017261	0.08			0.961		0.00		
701.58	2493.84	1.303	2495.141	28.0	10.81	1.816	2496.957	0.00	1.804	2.50	0.00	0.00	0	0.00
3.57	0.04711					.015215	0.05			0.961		0.00		
705.15	2494.01	1.354	2495.360	28.0	10.31	1.652	2497.012	0.00	1.804	2.50	0.00	0.00	0	0.00
2.89	0.04711					.013424	0.04			0.961		0.00		
708.04	2494.14	1.407	2495.549	28.0	9.83	1.501	2497.050	0.00	1.804	2.50	0.00	0.00	0	0.00
2.28	0.04711					.011855	0.03			0.961		0.00		
710.32	2494.25	1.463	2495.712	28.0	9.37	1.364	2497.076	0.00	1.804	2.50	0.00	0.00	0	0.00
1.75	0.04711					.010484	0.02			0.961		0.00		
712.07	2494.33	1.523	2495.855	28.0	8.94	1.240	2497.095	0.00	1.804	2.50	0.00	0.00	0	0.00
1.31	0.04711					.009286	0.01			0.961		0.00		
713.38	2494.39	1.586	2495.980	28.0	8.52	1.128	2497.108	0.00	1.804	2.50	0.00	0.00	0	0.00
0.92	0.04711					.008237	0.01			0.961		0.00		

ST-RH036363

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P


PAGE 3

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH JC14 - 28 CFS

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.ELEV.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SF AVE	HF			NORM DEPTH				
714.30	2494.44	1.653	2496.090	28.0	8.13	1.025	2497.115	0.00	1.804	2.50	0.00	0.00	0	0.00
0.53	0.04711					.007323	0.00			0.961		0.00		
714.83	2494.46	1.725	2496.187	28.0	7.75	0.932	2497.119	0.00	1.804	2.50	0.00	0.00	0	0.00
0.17	0.04711					.006524	0.00			0.961		0.00		
715.00	2494.47	1.804	2496.274	28.0	7.38	0.846	2497.120	0.00	1.804	2.50	0.00	0.00	0	0.00

ST-RH036364



STORM DRAIN SYSTEM

INLET	SIZE	Q _{inlet}	Q _{intercept}	Q _{bypass}	Grade/Sump
A	8.5	15	6	9	G
B	11.5	16	7	9	G
C	14.5	33	14	19	G
D	8.5	33	14	19	G
E	11.5	12	7	7	G
F	8.5	13	5	6	G
G	11.5	67	11	56	S

SD PIPES

PIPE	Q _{pipe}	Size
1	13	A
2	28	B
3	12	C
4	53	D
5	64	36

REVISIONS

DESIGNED RJM
 DRAWN RJM
 CHECKED _____
 APPROVED _____
 DATE 3/02/06

DWN

APVD

APVD

DATE



RHODES HOMES ARIZONA
 GOLDEN VALLEY RANCH
 AREA 1 - PHASE B

COMMON LOT E
 NODE J-C17

SCALE 1" = 50'

NO.

A

REV.

0

ST-RH036366

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT E
NODE J-C17
INLET A

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0119
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	15.000
T	Width of Spread (ft)	18.94

Gutter Flow

Eo	Gutter Flow Ratio	0.233
d	Depth of Flow (ft)	0.47
V	Average Velocity (ft/sec)	4.10

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	31.84	4.25	0.08	1.142	13.858
Parallel Bar P-1-7/8	1.50	2.88	0.32	4.491	9.368
Combination			0.38	5.632	9.368

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT E
NODE J-C17
INLET B

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0119
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	16.000
T	Width of Spread (ft)	19.42

Gutter Flow

Bo	Gutter Flow Ratio	0.227
d	Depth of Flow (ft)	0.48
V	Average Velocity (ft/sec)	4.16

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	33.06	5.75	0.07	1.174	14.826
Parallel Bar P-1-7/8	1.50	4.38	0.42	6.193	8.634
Combination			0.46	7.366	8.634

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway Pavements

Inlets on Grade
Date: 03/15/2006

Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT E
NODE J-C17
INLET C

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0050
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	33.000
T	Width of Spread (ft)	30.33

Gutter Flow

Eo	Gutter Flow Ratio	0.142
d	Depth of Flow (ft)	0.70
V	Average Velocity (ft/sec)	3.56

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	41.02	5.75	0.06	1.957	31.043
Parallel Bar P-1-7/8	1.50	4.38	0.40	12.308	18.734
Combination			0.43	14.266	18.734

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT E
NODE J-C17
INLET D

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0062
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	33.000
T	Width of Spread (ft)	29.12

Gutter Flow

Eo	Gutter Flow Ratio	0.148
d	Depth of Flow (ft)	0.68
V	Average Velocity (ft/sec)	3.86

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	43.13	5.75	0.06	1.863	31.137
Parallel Bar P-1-7/8	1.50	4.38	0.38	11.702	19.435
Combination			0.41	13.565	19.435

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT E
NODE J-C17
INLET E

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0050
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	12.000
T	Width of Spread (ft)	20.55

Gutter Flow

Bo	Gutter Flow Ratio	0.214
d	Depth of Flow (ft)	0.51
V	Average Velocity (ft/sec)	2.79

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	23.12	4.25	0.10	1.249	10.751
Parallel Bar P-1-7/8	1.50	2.88	0.38	4.073	6.678
Combination			0.44	5.322	6.678

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway Pavements

Inlets on Grade
Date: 03/15/2006

Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

COMMON LOT E
NODE J-C17
INLET F

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0057
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	13.000
T	Width of Spread (ft)	20.66

Gutter Flow

Eo	Gutter Flow Ratio	0.212
d	Depth of Flow (ft)	0.51
V	Average Velocity (ft/sec)	2.99

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	24.93	5.75	0.10	1.258	11.742
Parallel Bar P-1-7/8	1.50	4.38	0.51	5.948	5.795
Combination			0.55	7.205	5.795

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway Pavements

Inlets on Sag
Date: 03/10/2006

Project No. :18449
Project Name.:GOLDEN VALLEY RANCH
Computed by :rjm

Project Description

SAG INLETS - ALL PODS
MODIFIED "C" L-11.5
Node I-417 INLET 4
Inlets on Sag: Sweeper Combination Inlet

Roadway and Discharge Data

	Cross Slope	Composite/Dep
Sx	Pavement Cross Slope (ft/ft)	0.0100
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00

Inlet Interception

	Inlet Type *Sag*	Curb-Opening
L	Curb-Opening Length (ft)	5.75
H	Curb-Opening Height (in)	6.00
	Inlet Type *Sag*	Parallel Bar P-1-7/8
T	Width of Spread (ft)	39.48
WGR	Grate Width (ft)	1.50
L	Grate Length (ft)	4.38
	Inlet Type *Sag*	Sweeper Combination
d_ave	Depth of Flow (ft)	0.526
d_curb	Depth at Curb (ft)	0.671
Qi	Intercepted Flow (cfs)	11.000

Note: The curb opening length in the input screen is the total of the curb opening including its length along the grate.

Worksheet

Worksheet for Triangular Channel

Project Description	
Worksheet	COMMON LOT E - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Input Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	56.00 cfs

Results	
Depth	0.82 ft
Flow Area	19.3 ft ²
Wetted Perimeter	47.22 ft
Top Width	47.19 ft
Critical Depth	0.75 ft
Critical Slope	0.008092 ft/ft
Velocity	2.90 ft/s
Velocity Head	0.13 ft
Specific Energy	0.95 ft
Froude Number	0.80
Flow Type	Subcritical

VELOCITY x DEPTH.


$$2.9 \times 0.8 = 2.3 < 6.0$$

Cross Section

Cross Section for Triangular Channel

Project Description	
Worksheet	COMMON LOT E - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth


Section Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Depth	0.82 ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	56.00 cfs




Q:\184449\dwg\design\SD_PRO\POD1\WLR_STA93+90.dwg, 3/16/2006 5:50:46 PM, \\vg-ps1\hp5100-eng, 1:1

\$\$\$\$\$FILENAME\$\$\$\$\$ STANLEY CONSULTANTS

CADD A1-R3 © STANLEY CONSULTANTS



 Stanley Consultants INC.					SCALE 1:1																																				
<table border="1"> <thead> <tr> <th>REVISIONS</th> <th>DWN</th> <th>APVD</th> <th>APVD</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>DESIGNED RJM</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DRAWN RN</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>CHECKED</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>APPROVED</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>APPROVED</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DATE DATE</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>					REVISIONS	DWN	APVD	APVD	DATE	DESIGNED RJM					DRAWN RN					CHECKED					APPROVED					APPROVED					DATE DATE					NO. A	
REVISIONS	DWN	APVD	APVD	DATE																																					
DESIGNED RJM																																									
DRAWN RN																																									
CHECKED																																									
APPROVED																																									
APPROVED																																									
DATE DATE																																									
RHODES HOMES ARIZONA GOLDEN VALLEY RANCH AREA 1 - PHASE B					COMMON LOT E NODE J-C17																																				
					REV. 0																																				

F 0 5 1 5 P

PAGE NO 3

WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS -

GOLDEN VALLEY RANCH

HEADING LINE NO 2 IS -

GOLDEN VALLEY

HEADING LINE NO 3 IS -

LATERAL WITH 28 CFS IN POD 2 - J-C17 STA 93 + ON WLPR

ST-RH036377

DATE: 3/15/2006
TIME: 13:11

F0515P
WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING

PAGE 1

CARD	SECT	CHN	NO OF	AVE PIER	HEIGHT 1	BASE	ZL	ZR	INV	Y(1)	Y(2)	Y(3)	Y(4)	Y(5)	Y(6)	Y(7)	Y(8)	Y(9)	Y(10)
CODE	NO	TYPE	PIERS	WIDTH	DIAMETER	WIDTH			DROP										
CD	48	4			4.00														
CD	18	4			1.50														
CD	36	4			3.00														
CD	30	4			2.50														
CD	24	4			2.00														

F 0 5 1 5 P

PAGE NO 2

WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	1	IS A	SYSTEM OUTLET	*	*	*										
	U/S DATA	STATION	INVERT	SECT	W S ELEV											
		100.00	2482.05	36	2485.11											
ELEMENT NO	2	IS A	REACH	*	*	*										
	U/S DATA	STATION	INVERT	SECT	N											
		302.00	2483.24	36	0.013											
										RADIUS	ANGLE	ANG PT	MAN H			
										0.00	0.00	45.00	0			
ELEMENT NO	3	IS A	JUNCTION	*	*	*	*	*	*							
	U/S DATA	STATION	INVERT	SECT	LAT-1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4			
		307.00	2483.36	36	24	0	0.013	11.0	0.0	2483.36	0.00	90.00	0.00			
ELEMENT NO	4	IS A	REACH	*	*	*										
	U/S DATA	STATION	INVERT	SECT	N											
		332.00	2483.74	36	0.013											
										RADIUS	ANGLE	ANG PT	MAN H			
										0.00	0.00	10.00	0			
ELEMENT NO	5	IS A	JUNCTION	*	*	*	*	*	*							
	U/S DATA	STATION	INVERT	SECT	LAT-1	LAT-2	N	Q3	Q4	INVERT-3	INVERT-4	PHI 3	PHI 4			
		337.00	2483.78	36	18	18	0.013	13.0	12.0	2483.78	2483.78	90.00	90.00			
WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS																
ELEMENT NO	6	IS A	REACH	*	*	*										
	U/S DATA	STATION	INVERT	SECT	N											
		375.00	2484.29	30	0.013											
										RADIUS	ANGLE	ANG PT	MAN H			
										0.00	0.00	0.00	0			

WARNING - ADJACENT SECTIONS ARE NOT IDENTICAL - SEE SECTION NUMBERS AND CHANNEL DEFINITIONS

NO EDIT ERRORS ENCOUNTERED-COMPUTATION IS NOW BEGINNING
 ** WARNING NO. 2 ** - WATER SURFACE ELEVATION GIVEN IS LESS THAN OR EQUALS INVERT ELEVATION IN HDWKDS, W.S.ELEV = INV + DC

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 1

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH 96 CFS IN POD 2 - J-C17

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL NO	AVBPR PIER
L/ELEM	SO					SF AVE	HF		NORM DEPTH			ZR	
100.00	2482.05	3.060	2485.110	64.0	9.05	1.273	2486.383	0.00	2.570	3.00	0.00	0.00	0 0.00
202.00	0.00589					.009207	1.86		3.000			0.00	
302.00	2483.24	3.919	2487.159	64.0	9.05	1.273	2488.432	0.00	2.570	3.00	0.00	0.00	0 0.00
JUNCT STR	0.02400					.007761	0.04					0.00	
307.00	2483.36	4.638	2487.998	53.0	7.50	0.873	2488.871	0.00	2.366	3.00	0.00	0.00	0 0.00
25.00	0.01520					.006314	0.16		1.751			0.00	
332.00	2483.74	4.444	2488.184	53.0	7.50	0.873	2489.057	0.00	2.366	3.00	0.00	0.00	0 0.00
JUNCT STR	0.00800					.004038	0.02					0.00	
337.00	2483.78	5.683	2489.463	28.0	5.70	0.505	2489.968	0.00	1.804	2.50	0.00	0.00	0 0.00
38.00	0.01342					.004660	0.18		1.380			0.00	
375.00	2484.29	5.350	2489.640	28.0	5.70	0.505	2490.145	0.00	1.804	2.50	0.00	0.00	0 0.00

ST-RH036380

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH 96 CFS IN POD 2 - J-C17


100.00	.	I	.	.	.	C	X	.	.	E	R
105.61
111.22
116.84
122.45
128.06
133.67
139.29
144.90
150.51
156.12
161.73
167.35
172.96
178.57
184.18
189.80
195.41
201.02
206.63
212.24
217.86
223.47
229.08
234.69
240.31
245.92
251.53
257.14
262.76
268.37
273.98
279.59
285.20
290.82
296.43
302.04	.	.	I	C	.	H	.	W	.	E	JX	.
307.65	.	.	I	C	.	H	.	W	.	E	.	E	.	.	R	.
313.27
318.88
324.49
330.10
335.71	.	.	I	C	.	H	.	W	.	E	.	.	JX	.
341.33	.	.	I	C	.	H	.	W	.	E	.	.	R	.
346.94
352.55
358.16
363.78
369.39
375.00	.	.	.	I	C	.	H	.	.	.	W	.	E	.	R
	2482.05	2482.86	2483.67	2484.48	2485.29	2486.10	2486.91	2487.72	2488.53	2489.34	2490.15									

NOTES

1. GLOSSARY

- I = INVERT ELEVATION
- C = CRITICAL DEPTH
- W = WATER SURFACE ELEVATION
- H = HEIGHT OF CHANNEL
- E = ENERGY GRADE LINE
- X = CURVES CROSSING OVER
- B = BRIDGE ENTRANCE OR EXIT
- Y = WALL ENTRANCE OR EXIT

2. STATIONS FOR POINTS AT A JUMP MAY NOT BE PLOTTED EXACTLY



STORM DRAIN SYSTEM

INLET	SIZE	Qinlet	Qintercept	Qbypass	Grade/Sump
A	8.5	27	8	19	G
B	11.5	27	11	16	G
C	11.5	19	8	11	G
D	11.5	16	7	9	G

SD PIPES

PIPE	Qpipe	Size
1	19	A
2	34	24

DESIGNED RJM				
DRAWN RJM				
CHECKED				
APPROVED				
APPROVED				
DATE 3/02/06				



RHODES HOMES ARIZONA
GOLDEN VALLEY RANCH
AREA 1 - PHASE B

H STREET
NODE J-C21

SCALE 1" = 50'

NO.	REV.
A	0

STANLEY CONSULTANTS
CADD A1-R3

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

H STREET
NODE J-C21
INLET A

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0074
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	27.000
T	Width of Spread (ft)	26.10

Gutter Flow

Eo	Gutter Flow Ratio	0.166
d	Depth of Flow (ft)	0.62
V	Average Velocity (ft/sec)	3.92

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	40.16	4.25	0.06	1.635	25.365
Parallel Bar P-1-7/8	1.50	2.88	0.27	6.793	18.572
Combination			0.31	8.428	18.572

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

H STREET
NODE J-C21
INLET B

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0074
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	27.000
T	Width of Spread (ft)	26.10

Gutter Flow

Bo	Gutter Flow Ratio	0.166
d	Depth of Flow (ft)	0.62
V	Average Velocity (ft/sec)	3.92

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	40.16	5.75	0.06	1.635	25.365
Parallel Bar P-1-7/8	1.50	4.38	0.39	9.772	15.592
Combination			0.42	11.408	15.592

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

H STREET
NODE J-C21
INLET C

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0164
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	19.000
T	Width of Spread (ft)	19.51

Gutter Flow

Eo	Gutter Flow Ratio	0.226
d	Depth of Flow (ft)	0.49
V	Average Velocity (ft/sec)	4.90

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	39.20	5.75	0.06	1.179	17.821
Parallel Bar P-1-7/8	1.50	4.38	0.38	6.725	11.096
Combination			0.42	7.904	11.096

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Grade
Date: 03/15/2006Project No. :18476-Pod1
Project Name.:Golden Valley Ranch - Pod 1
Computed by :rjm

Project Description

H STREET
NODE J-C21
INLET D

Inlets on Grade: Curb Opening, Grate Inlet

Roadway and Discharge Data

	Cross Slope	Composite
S	Longitudinal Slope (ft/ft)	0.0164
Sx	Pavement Cross Slope (ft/ft)	0.0200
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00
Q	Discharge (cfs)	16.000
T	Width of Spread (ft)	18.25


Gutter Flow

Eo	Gutter Flow Ratio	0.242
d	Depth of Flow (ft)	0.46
V	Average Velocity (ft/sec)	4.70

Inlet Interception

INLET INTERCEPTION	LT or WGR (ft)	L (ft)	E	Qi (cfs)	Qb (cfs)
Curb Opening	35.45	5.75	0.07	1.096	14.904
Parallel Bar P-1-7/8	1.50	4.38	0.40	5.971	8.933
Combination			0.44	7.067	8.933

Note: The curb opening length in the input screen is the total length of the curb opening including its length along the grate.



HS 1" = 100'
VS 1" = 10'


LEGEND

---	Existing Grade
—	Finish Grade
...	HGL

Q:\18449\dwg\design\SD_PRO\POD1\WLR_STA85+08.dwg, 3/16/2006 5:47:11 PM, \\vg-ps1\hp5100-eng, 1:1

\$\$\$\$\$FILENAME\$\$\$\$\$

CADD A1-R3 © STANLEY CONSULTANTS

 Stanley Consultants INC.					SCALE NO. A REV. 0	
REVISIONS DESIGNED RJM DRAWN RN CHECKED APPROVED APPROVED DATE DATE	DWN APVD APVD DATE	RHODES VALLEY ARIZONA GOLDEN VALLEY RANCH			H STREET NODE J-C21 DRAWING_TITLE	

ST-RH036387

F 0 5 1 5 P

PAGE NO 3

WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS -

GOLDEN VALLEY RANCH

HEADING LINE NO 2 IS -

GOLDEN VALLEY

HEADING LINE NO 3 IS -

LATERAL WITH FLOW 19 CFS J-C21 STA 85 + WLPR

ST-RH036388

DATE: 3/20/2006
TIME: 8:18

F0515P
WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING

PAGE 1

CARD CODE	SECT NO	CHN TYPE	NO OF PIERS	AVE PIER WIDTH	HEIGHT 1 DIAMETER	BASE WIDTH	ZL	ZR	INV DROP	Y(1)	Y(2)	Y(3)	Y(4)	Y(5)	Y(6)	Y(7)	Y(8)	Y(9)	Y(10)
CD	24	4			2.00														
CD	30	4			2.50														
CD	18	4			1.50														

ST-RH036389

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 1

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH FLOW 35CFS J-C21

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SF AVE	HF			NORM DEPTH				
100.00	2474.18	7.700	2481.880	34.0	10.82	1.818	2483.698	0.00	1.911	2.00	0.00	0.00	0	0.00
26.12	0.12979					.022588	0.59			0.900		0.00		
126.12	2477.57	4.907	2482.478	34.0	10.82	1.818	2484.296	0.00	1.911	2.00	0.00	0.00	0	0.00
HYDRAULIC JUMP														0.00
126.12	2477.57	0.996	2478.567	34.0	21.75	7.348	2485.915	0.00	1.911	2.00	0.00	0.00	0	0.00
6.27	0.12979					.089790	0.56			0.900		0.00		
132.39	2478.38	1.007	2479.390	34.0	21.44	7.136	2486.526	0.00	1.911	2.00	0.00	0.00	0	0.00
12.95	0.12979					.082740	1.07			0.900		0.00		
145.34	2480.07	1.046	2481.111	34.0	20.43	6.483	2487.594	0.00	1.911	2.00	0.00	0.00	0	0.00
9.65	0.12979					.072956	0.70			0.900		0.00		
154.99	2481.32	1.087	2482.404	34.0	19.48	5.895	2488.299	0.00	1.911	2.00	0.00	0.00	0	0.00
7.54	0.12979					.064385	0.49			0.900		0.00		
162.53	2482.30	1.130	2483.425	34.0	18.58	5.360	2488.785	0.00	1.911	2.00	0.00	0.00	0	0.00
6.06	0.12979					.056871	0.34			0.900		0.00		
168.59	2483.08	1.175	2484.258	34.0	17.72	4.874	2489.132	0.00	1.911	2.00	0.00	0.00	0	0.00
4.97	0.12979					.050296	0.25			0.900		0.00		
173.56	2483.73	1.223	2484.950	34.0	16.89	4.430	2489.380	0.00	1.911	2.00	0.00	0.00	0	0.00
4.14	0.12979					.044540	0.18			0.900		0.00		
177.70	2484.26	1.273	2485.537	34.0	16.11	4.028	2489.565	0.00	1.911	2.00	0.00	0.00	0	0.00
3.46	0.12979					.039507	0.14			0.900		0.00		
181.16	2484.71	1.327	2486.040	34.0	15.35	3.659	2489.699	0.00	1.911	2.00	0.00	0.00	0	0.00
2.90	0.12979					.035130	0.10			0.900		0.00		

ST-RH036391

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 2

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH FLOW 35CFS J-C21

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD.EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SF AVE	HF			NORM DEPTH		ZR		
184.06	2485.09	1.385	2486.475	34.0	14.64	3.326	2489.801	0.00	1.911	2.00	0.00	0.00	0	0.00
2.43	0.12979					.031331	0.08			0.900		0.00		
186.49	2485.41	1.448	2486.853	34.0	13.96	3.025	2489.878	0.00	1.911	2.00	0.00	0.00	0	0.00
2.05	0.12979					.028033	0.06			0.900		0.00		
188.54	2485.67	1.515	2487.186	34.0	13.31	2.750	2489.936	0.00	1.911	2.00	0.00	0.00	0	0.00
1.67	0.12979					.025198	0.04			0.900		0.00		
190.21	2485.89	1.590	2487.478	34.0	12.69	2.499	2489.977	0.00	1.911	2.00	0.00	0.00	0	0.00
1.33	0.12979					.022829	0.03			0.900		0.00		
191.54	2486.06	1.675	2487.735	34.0	12.10	2.273	2490.008	0.00	1.911	2.00	0.00	0.00	0	0.00
0.98	0.12979					.020949	0.02			0.900		0.00		
192.52	2486.19	1.775	2487.962	34.0	11.53	2.065	2490.027	0.00	1.911	2.00	0.00	0.00	0	0.00
0.48	0.12979					.019878	0.01			0.900		0.00		
193.00	2486.25	1.911	2488.161	34.0	11.00	1.878	2490.039	0.00	1.911	2.00	0.00	0.00	0	0.00
JUNCT STR	0.13000					.013336	0.07					0.00		
198.00	2486.90	3.908	2490.808	19.0	6.05	0.568	2491.376	0.00	1.568	2.00	0.00	0.00	0	0.00
152.00	0.01336					.007054	1.07			1.262		0.00		
350.00	2488.93	2.950	2491.880	19.0	6.05	0.568	2492.448	0.00	1.568	2.00	0.00	0.00	0	0.00

ST-RH036392

GOLDEN VALLEY RANCH
GOLDEN VALLEY
LATERAL WITH FLOW 35CFS J-C21


[illegible]

NOTES

1. GLOSSARY

I = INVERT ELEVATION
C = CRITICAL DEPTH
W = WATER SURFACE ELEVATION
H = HEIGHT OF CHANNEL
E = ENERGY GRADE LINE
X = CURVES CROSSING OVER
B = BRIDGE ENTRANCE OR EXIT
Y = WALL ENTRANCE OR EXIT

2. STATIONS FOR POINTS AT A JUMP MAY NOT BE PLOTTED EXACTLY



STORM DRAIN SYSTEM

INLET	SIZE	Qinlet	Qintercept	Qbypass	Grade/Sump
A	14.5	73	12	61	S

SD PIPES

PIPE	Qpipe	Size
1	12	A

REVISIONS	DWN	APVD	DATE
DESIGNED RJM			
DRAWN RJM			
CHECKED			
APPROVED			
DATE 3/02/06			



RHODES HOMES ARIZONA
GOLDEN VALLEY RANCH
AREA 1 - PHASE B

COMMON LOT D
NODE J-C25

SCALE 1" = 60'

NO.	REV.
A	0

\$\$\$ FILENAME: STANLEY CONSULTANTS CADD AT-R3

FHWA Urban Drainage Design Program, HY-22
Drainage of Highway PavementsInlets on Sag
Date: 03/10/2006Project No. :18449
Project Name.:GOLDEN VALLEY RANCH
Computed by :rjm

Project Description
 SAG INLETS - ALL PODS
 MODIFIED "C" L-14.5
 POPE J-C25 INLET A Common Lot "D"
 Inlets on Sag: Sweeper Combination Inlet

Roadway and Discharge Data

	Cross Slope	Composite/Dep
Sx	Pavement Cross Slope (ft/ft)	0.0100
Sw	Gutter Cross Slope (ft/ft)	0.0833
n	Manning's Coefficient	0.016
W	Gutter Width (ft)	1.50
a	Gutter Depression (inch)	2.00

Inlet Interception

	Inlet Type *Sag*	Curb-Opening
L	Curb-Opening Length (ft)	5.75
H	Curb-Opening Height (in)	6.00
	Inlet Type *Sag*	Parallel Bar P-1-7/8
T	Width of Spread (ft)	39.39
WGR	Grate Width (ft)	1.50
L	Grate Length (ft)	5.88
	Inlet Type *Sag*	Sweeper Combination
d _{ave}	Depth of Flow (ft)	0.525
d _{curb}	Depth at Curb (ft)	0.671
Qi	Intercepted Flow (cfs)	12.000

Note: The curb opening length in the input screen is the total of the curb opening including its length along the grate.

Worksheet

Worksheet for Triangular Channel

Project Description	
Worksheet	COMMON LOT D - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Input Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	61.00 cfs

Results	
Depth	0.85 ft
Flow Area	20.6 ft ²
Wetted Perimeter	48.76 ft
Top Width	48.73 ft
Critical Depth	0.77 ft
Critical Slope	0.008000 ft/ft
Velocity	2.96 ft/s
Velocity Head	0.14 ft
Specific Energy	0.98 ft
Froude Number	0.80
Flow Type	Subcritical

VELOCITY x DEPTH.


$$3.0 \times 0.9 = 2.7 \text{ cfs}$$

Cross Section

Cross Section for Triangular Channel

Project Description	
Worksheet	COMMON LOT D - Drainage Easement - Triangular
Flow Element	Triangular Channel
Method	Manning's Formula
Solve For	Channel Depth


Section Data	
Mannings Coefficient	0.020
Channel Slope	0.005000 ft/ft
Depth	0.85 ft
Left Side Slope	28.80 H : V
Right Side Slope	28.80 H : V
Discharge	61.00 cfs




Q:\18449\dwg\design\SD_PRO\POD1\6str_CULDESAC.dwg, 3/16/2006 5:44:03 PM, \\vg-ps1\hp5100-eng, 1:1

\$\$\$\$\$FILENAME\$\$\$\$\$

CADD A1-R3 © STANLEY CONSULTANTS



<div style="text-align: center;">  Stanley Consultants INC. </div>					SCALE 1:1																																												
<table border="1"> <thead> <tr> <th>REVISIONS</th> <th>APVD</th> <th>APVD</th> <th>APVD</th> <th>DATE</th> </tr> </thead> <tbody> <tr> <td>DESIGNED RJM</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DRAWN RN</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>CHECKED</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>APPROVED</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>APPROVED</td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td>DATE</td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>					REVISIONS	APVD	APVD	APVD	DATE	DESIGNED RJM					DRAWN RN					CHECKED					APPROVED					APPROVED					DATE					<table border="1"> <tr> <td colspan="2"> RHODES HOMES ARIZONA GOLDEN VALLEY RANCH AREA 1 - PHASE B </td> <td colspan="2"> COMMON LOT D NODE J-C25 </td> </tr> <tr> <td colspan="2"> NO. A </td> <td colspan="2"> REV. 0 </td> </tr> </table>		RHODES HOMES ARIZONA GOLDEN VALLEY RANCH AREA 1 - PHASE B		COMMON LOT D NODE J-C25		NO. A		REV. 0	
REVISIONS	APVD	APVD	APVD	DATE																																													
DESIGNED RJM																																																	
DRAWN RN																																																	
CHECKED																																																	
APPROVED																																																	
APPROVED																																																	
DATE																																																	
RHODES HOMES ARIZONA GOLDEN VALLEY RANCH AREA 1 - PHASE B		COMMON LOT D NODE J-C25																																															
NO. A		REV. 0																																															

P O S T E D

PAGE NO 3

WATER SURFACE PROFILE - TITLE CARD LISTING

HEADING LINE NO 1 IS -

GOLDEN VALLEY RANCH

HEADING LINE NO 2 IS -

GOLDEN VALLEY

HEADING LINE NO 3 IS -

6 STREET TO GOLF COURSE J-C25 IN POD1 12CFS

ST-RH036399

DATE: 3/14/2006
TIME: 13:23

F0515P
WATER SURFACE PROFILE - CHANNEL DEFINITION LISTING

PAGE 1

CARD	SECT	CHN	NO OF	AVE PIER	HEIGHT 1	BASE	ZL	ZR	INV	Y(1)	Y(2)	Y(3)	Y(4)	Y(5)	Y(6)	Y(7)	Y(8)	Y(9)	Y(10)
CODE	NO	TYPE	PIERS	WIDTH	DIAMETER	WIDTH			DROP										
CD	30	4				2.50													

F 0 5 1 5 P

PAGE NO 2

WATER SURFACE PROFILE - ELEMENT CARD LISTING

ELEMENT NO	1	IS A SYSTEM OUTLET	*	*	*								
		U/S DATA	STATION	INVERT	SECT							W S ELEV	
			100.00	2479.50	30							2484.20	
ELEMENT NO	2	IS A REACH	*	*	*								
		U/S DATA	STATION	INVERT	SECT		N					RADIUS	ANGLE
			420.00	2484.56	30		0.013					0.00	0.00
												ANG PT	MAN H
												0.00	0
ELEMENT NO	3	IS A SYSTEM HEADWORKS	*	*	*								
		U/S DATA	STATION	INVERT	SECT							W S ELEV	
			420.00	2484.56	30							0.00	

NO EDIT ERRORS ENCOUNTERED-COMPUTATION IS NOW BEGINNING

** WARNING NO. 2 ** - WATER SURFACE ELEVATION GIVEN IS LESS THAN OR EQUALS INVERT ELEVATION IN HDWKDS, W.S.ELEV = INV + DC

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 1

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
6 STREET TO GOLF COURSE J-C25

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD-EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVEPR
L/ELEM	SO					SF AVE	HF		NORM DEPTH			ZR		
100.00	2479.50	4.700	2484.200	12.0	2.44	0.093	2484.293	0.00	1.162	2.50	0.00	0.00	0	0.00
147.10	0.01581					.000848	0.12		0.820			0.00		
247.10	2481.83	2.500	2484.326	12.0	2.44	0.093	2484.419	0.00	1.162	2.50	0.00	0.00	0	0.00
14.76	0.01581					.000795	0.01		0.820			0.00		
261.86	2482.06	2.268	2484.327	12.0	2.56	0.102	2484.429	0.00	1.162	2.50	0.00	0.00	0	0.00
8.29	0.01581					.000775	0.01		0.820			0.00		
270.15	2482.19	2.133	2484.323	12.0	2.69	0.112	2484.435	0.00	1.162	2.50	0.00	0.00	0	0.00
6.67	0.01581					.000839	0.01		0.820			0.00		
276.82	2482.30	2.022	2484.318	12.0	2.82	0.124	2484.442	0.00	1.162	2.50	0.00	0.00	0	0.00
5.68	0.01581					.000923	0.01		0.820			0.00		
282.50	2482.39	1.925	2484.311	12.0	2.96	0.136	2484.447	0.00	1.162	2.50	0.00	0.00	0	0.00
5.03	0.01581					.001024	0.01		0.820			0.00		
287.53	2482.47	1.837	2484.302	12.0	3.10	0.149	2484.451	0.00	1.162	2.50	0.00	0.00	0	0.00
4.44	0.01581					.001143	0.01		0.820			0.00		
291.97	2482.53	1.757	2484.292	12.0	3.25	0.164	2484.456	0.00	1.162	2.50	0.00	0.00	0	0.00
3.96	0.01581					.001280	0.01		0.820			0.00		
295.93	2482.60	1.683	2484.281	12.0	3.41	0.181	2484.462	0.00	1.162	2.50	0.00	0.00	0	0.00
3.54	0.01581					.001439	0.01		0.820			0.00		
299.47	2482.65	1.614	2484.268	12.0	3.58	0.199	2484.467	0.00	1.162	2.50	0.00	0.00	0	0.00
1.14	0.01581					.001551	0.00		0.820			0.00		
300.61	2482.67	1.594	2484.266	12.0	3.63	0.205	2484.471	0.00	1.162	2.50	0.00	0.00	0	0.00
HYDRAULIC JUMP												0.00		

ST-RH036402

LICENSEE: STANLEY CONSULTANTS, INC.

F0515P

PAGE 2

WATER SURFACE PROFILE LISTING

GOLDEN VALLEY RANCH
GOLDEN VALLEY
6 STREET TO GOLF COURSE J-C25

STATION	INVERT ELEV	DEPTH OF FLOW	W.S. ELEV	Q	VEL	VEL HEAD	ENERGY GRD. EL.	SUPER ELEV	CRITICAL DEPTH	HGT/ DIA	BASE/ ID NO.	ZL	NO PIER	AVBPR
L/ELEM	SO					SF AVE	HF		NORM DEPTH			ZR		
300.61	2482.67	0.820	2483.492	12.0	8.57	1.139	2484.631	0.00	1.162	2.50	0.00	0.00	0	0.00
54.32	0.01581					.015065	0.82		0.820			0.00		
354.93	2483.53	0.842	2484.373	12.0	8.25	1.058	2485.431	0.00	1.162	2.50	0.00	0.00	0	0.00
27.57	0.01581					.013410	0.37		0.820			0.00		
382.50	2483.97	0.872	2484.839	12.0	7.87	0.961	2485.800	0.00	1.162	2.50	0.00	0.00	0	0.00
13.91	0.01581					.011754	0.16		0.820			0.00		
396.41	2484.19	0.903	2485.090	12.0	7.50	0.875	2485.965	0.00	1.162	2.50	0.00	0.00	0	0.00
8.63	0.01581					.010304	0.09		0.820			0.00		
405.04	2484.32	0.935	2485.258	12.0	7.16	0.795	2486.053	0.00	1.162	2.50	0.00	0.00	0	0.00
5.65	0.01581					.009036	0.05		0.820			0.00		
410.69	2484.41	0.969	2485.382	12.0	6.82	0.723	2486.105	0.00	1.162	2.50	0.00	0.00	0	0.00
3.89	0.01581					.007928	0.03		0.820			0.00		
414.58	2484.47	1.004	2485.478	12.0	6.50	0.657	2486.135	0.00	1.162	2.50	0.00	0.00	0	0.00
2.57	0.01581					.006960	0.02		0.820			0.00		
417.15	2484.51	1.041	2485.556	12.0	6.20	0.597	2486.153	0.00	1.162	2.50	0.00	0.00	0	0.00
1.68	0.01581					.006111	0.01		0.820			0.00		
418.83	2484.54	1.079	2485.621	12.0	5.91	0.543	2486.164	0.00	1.162	2.50	0.00	0.00	0	0.00
0.90	0.01581					.005369	0.00		0.820			0.00		
419.73	2484.56	1.119	2485.675	12.0	5.64	0.494	2486.169	0.00	1.162	2.50	0.00	0.00	0	0.00
0.27	0.01581					.004712	0.00		0.820			0.00		
420.00	2484.56	1.162	2485.722	12.0	5.37	0.448	2486.170	0.00	1.162	2.50	0.00	0.00	0	0.00

ST-RH036403

GOLDEN VALLEY RANCH
GOLDEN VALLEY
6 STREET TO GOLF COURSE J-C25

[illegible]

NOTES

1. GLOSSARY

- I = INVERT ELEVATION
C = CRITICAL DEPTH
W = WATER SURFACE ELEVATION
H = HEIGHT OF CHANNEL
E = ENERGY GRADE LINE
X = CURVES CROSSING OVER
B = BRIDGE ENTRANCE OR EXIT
Y = WALL ENTRANCE OR EXIT

2. STATIONS FOR POINTS AT A JUMP MAY NOT BE PLOTTED EXACTLY

GOLDEN VALLEY RANCH


APPENDIX C

STREET CAPACITY (LOCAL STREETS)

Cross Section Cross Section for Irregular Channel

Project Description	
Worksheet	Local Str 50' Pl
Flow Element	Irregular Chani
Method	Manning's Forr
Solve For	Discharge

Section Data	
Mannings Coefficient	0.014
Channel Slope	0.005000 ft/ft
Water Surface Elev.	100.67 ft
Elevation Range	100.00 to 100.67
Discharge	68.88 cfs



ST-RH036406

q:\18449\drainage calcs\street flow.fm2
12/30/05 11:35:56 AM

© Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666

Project Engineer: Information Services
FlowMaster v7.0 [7.0005]
Page 1 of 1

Table

Rating Table for Irregular Channel

Project Description	
Worksheet	Local Str 50'PL
Flow Element	Irregular Chan
Method	Manning's For
Solve For	Discharge

Input Data
Water Surface Elev. 00.67 ft

Options
Current Roughness Method: ved Lotter's Method
Open Channel Weighting: ved Lotter's Method
Closed Channel Weighting: Horton's Method

Attribute	Minimum	Maximum	Increment
Channel Slope (ft/ft)	0.005000	0.020000	0.000100

Channel Slope (ft/ft)	Discharge (cfs)	Velocity (ft/s)	Flow Area (ft²)	Wetted Perimeter (ft)	Top Width (ft)
0.005000	68.88	3.73	18.5	50.12	50.00
0.005100	69.57	3.76	18.5	50.12	50.00
0.005200	70.25	3.80	18.5	50.12	50.00
0.005300	70.92	3.84	18.5	50.12	50.00
0.005400	71.59	3.87	18.5	50.12	50.00
0.005500	72.25	3.91	18.5	50.12	50.00
0.005600	72.90	3.94	18.5	50.12	50.00
0.005700	73.55	3.98	18.5	50.12	50.00
0.005800	74.19	4.01	18.5	50.12	50.00
0.005900	74.83	4.05	18.5	50.12	50.00
0.006000	75.46	4.08	18.5	50.12	50.00
0.006100	76.09	4.12	18.5	50.12	50.00
0.006200	76.71	4.15	18.5	50.12	50.00
0.006300	77.32	4.18	18.5	50.12	50.00
0.006400	77.93	4.22	18.5	50.12	50.00
0.006500	78.54	4.25	18.5	50.12	50.00
0.006600	79.14	4.28	18.5	50.12	50.00
0.006700	79.74	4.31	18.5	50.12	50.00
0.006800	80.33	4.35	18.5	50.12	50.00
0.006900	80.92	4.38	18.5	50.12	50.00
0.007000	81.51	4.41	18.5	50.12	50.00
0.007100	82.09	4.44	18.5	50.12	50.00
0.007200	82.66	4.47	18.5	50.12	50.00
0.007300	83.23	4.50	18.5	50.12	50.00
0.007400	83.80	4.53	18.5	50.12	50.00
0.007500	84.37	4.56	18.5	50.12	50.00
0.007600	84.93	4.60	18.5	50.12	50.00
0.007700	85.48	4.63	18.5	50.12	50.00
0.007800	86.04	4.66	18.5	50.12	50.00
0.007900	86.59	4.69	18.5	50.12	50.00
0.008000	87.13	4.71	18.5	50.12	50.00
0.008100	87.68	4.74	18.5	50.12	50.00
0.008200	88.22	4.77	18.5	50.12	50.00
0.008300	88.75	4.80	18.5	50.12	50.00

Project Engineer: Information Services

FlowMaster v7.0 [7.0005]

q:\18449\drainage calcs\street flow.fm2

Stanley Consultants, Inc

12/30/05 11:35:00 AM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666

Page 1 of 4

ST-RH036407